



TEMPORARY DITCH CHECK, URETHANE FOAM/GEOTEXTILE (1) ONE EACH. [ON THE LEFT SIDE OF THE DITCH]

SILT DIKE UNIT ISOMETRIC

STAPLES SHALL BE PLACED WHERE THE UNITS OVERLAP AND IN THE CENTER OF THE 7' UNIT AS SHOWN ON THE DIAGRAM.

POINT 1 MUST BE HIGHER THAN POINT 2 TO INSURE THAT WATER FLOWS OVER THE DIKE AND NOT AROUND THE ENDS.

NOTE:
THE INSTALLATION SHOWN ABOVE WOULD BE PAID FOR AS TWO (2) EACH TEMPORARY DITCH CHECK, URETHANE FOAM/GEOTEXTILE.

SCALE: 1" = 5'

REVISIONS	DATE
DUAL DIMENSIONS	10/23/01
MODIFIED PAY ITEM NAME	3/8/05

Lake County
Division of Transportation

APPROVED BY: G. N. WIESNER
DATE: JULY 23, 1999

**TRIANGULAR SILT DIKE
INSTALLATION FOR
ROADWAY DITCH OR
DRAINAGE DITCH**

LC1005

REVISIONS	NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**FAU 2647 - BUTTERFIELD ROAD
TRIANGULAR SILT DIKE
INSTALLATION FOR
ROADWAY DITCH OR
DRAINAGE DITCH**

SCALE: NONE
DATE: 12/2/2005

DRAWN BY: N/A
CHECKED BY: N/A