

SIDE ROAD SCHEDULE

Station	O/S	Type	Butt Joint (Sq. Yd)	Bit. Conc. Incident (Ton)	Bit. Prime Incid. (Gallon)	Agg. Prime Incid. (Ton)	Agg. Shoulder (Ton)	BIT BINDER (TON)
185+04	Lt.	Twp. Road	85.8	14	9	0.3	6	3
224+66	Rt.	Twp. Road	80.2	13	8	0.2	6	3
277+71	Lt.	Twp. Road	90.9	14	10	0.3	7	4
TOTAL			256.9	41	27	0.8	19	10

FIELD ENTRANCE SCHEDULE

STATION	O/S	TYPE	WIDTH "W"	BIT. SURF CSE. INDEN. (TON)	BIT. MATL PRIM INCID (GAL)	AGG PRIME INCID. (TON)	AGG SURF TY B (TON)	BIT BINDER CSE (TON)
157+22	RT	FE	18	1.6	2	0.1	2.5	0.9
157+63	LT	FE	24	2.0	3	0.1	3.4	1.2
162+03	RT	FE	24	2.0	3	0.1	3.4	1.2
162+33	LT	FE	20	1.7	2	0.1	2.8	1.0
178+30	LT	FE	24	2.0	3	0.1	3.4	1.1
178+48	RT	FE	22	1.9	3	0.1	3.1	1.0
178+63	LT	FE	20	1.7	2	0.1	2.8	1.0
179+68	RT	FE	30	2.5	4	0.2	4.2	1.3
185+06	RT	FE	26	2.2	4	0.2	3.7	1.1
187+66	LT	FE	18	1.6	2	0.1	2.5	1.0
198+07	RT	FE	20	1.7	2	0.1	2.8	0.9
198+15	LT	FE	20	1.7	2	0.1	2.8	0.9
198+70	RT	FE	20	1.7	2	0.1	2.8	0.9
206+11	LT	FE	22	1.9	3	0.1	3.1	1.0
227+98	LT	FE	22	1.9	3	0.1	3.1	1.0
232+00	RT	FE	30	2.5	4	0.1	4.2	1.3
249+63	RT	FE	30	2.5	4	0.1	4.2	1.3
264+63	LT	FE	20	1.9	2	0.1	3.4	1.9
TOTAL				35.0	50	2.2	58.2	19.0

BITUMINOUS MATERIALS (PRIME COAT)
FOR INCIDENTAL BITUMINOUS SURFACING

LOCATION	QUANTITY
SIDE ROADS	27.0 GALLON
FIELD ENTRANCES	50.0 GALLON
PE'S, CE'S, & MAILBOXES	93.0 GALLON
TOTALS	170 GALLON

AGGREGATE (PRIME COAT)
FOR INCIDENTAL BITUMINOUS SURFACING

LOCATION	QUANTITY
SIDE ROADS	0.8 TON
FIELD ENTRANCES	2.2 TON
PE'S, CE'S, & MAILBOXES	3.0 TON
TOTALS	6.0 TON

INCIDENTAL BITUMINOUS SURFACING

LOCATION	QUANTITY
SIDE ROADS	41 TON
FIELD ENTRANCES	35 TON
PE'S, CE'S, & MAILBOXES	127 TON
TOTALS	203 TON

P.E. & C.E. TABLE (INCLUDING MAILBOXES)

STATION	O/S	TYPE	WIDTH "W"	RADIUS "R"	BIT. SURF CSE INCIDENT (TON)	BIT. MATL PRIM INCID. (GAL)	AGG. PRIME INCID. (TON)	AGG. SURF B (TON)	AGG SHLD (TON)	BIT. BINDER
166+16	Lt	PE&MB	22'	15'	9	7	0.2	2.1	2.2	1.0
162+87	Rt	PE&MB	14'	15'	7	5	0.2	1.3	2.2	0.6
169+10	Lt	PE	10'	15'	4	3	0.1	1.0	2.2	0.4
169+90	Lt	PE	10'	10'	3	2	0.1	1.0	1.6	0.4
178+76	Rt	PE&MB	14'	10'	6	4	0.1	1.3	1.6	0.6
202+56	Rt	PE&MB	16'	10'	6	4	0.1	1.5	1.6	0.7
208+80	Rt	PE&MB	20'	10'	6	5	0.2	1.9	1.6	0.9
216+33	Lt	CE	26'	40'	27	20	0.6	2.5	6.1	1.1
217+54	Lt	PE	32'	20'	13	9	0.3	3.0	3.0	1.4
217+54	Lt	MB	---	---	3	2	0.1	---	1.8	---
224+86	Lt	PE&MB	16'	15'	8	6	0.2	1.5	2.2	0.7
234+02	Lt	PE&MB	18'	15'	8	6	0.2	1.7	2.2	1.0
241+09	Lt	PE	18'	10'	4	3	0.1	1.7	1.6	1.0
273+38	Rt	CE	28'	35'	23	17	0.5	2.6	5.3	1.2
TOTAL					127	93	3	23.1	35.2	19.0

SIDE ROAD/ENTRANCE SCHEDULE

SCALE	APPROVED BY:	DRAWN BY:
DATE	REVISION	
		DRAWING NUMBER