

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	WILLIAMSON	55	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				
* [X1-(4,4-1,5,6,6-2)] R-1				

SUMMARY OF QUANTITIES

SHEET 1 OF 2

CODE NUMBER	ITEM DESCRIPTION CONSTRUCTION TYPE CODE	UNIT	90% FEDERAL / 10% STATE WILLIAMSON COUNTY	
			TOTAL QUANTITY	ROADWAY I 000
X0300471	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT	SQ YD	100,035	100,035
* X0300780	PIEZO ELECTRIC AXLE SENSOR CABLE IN CONDUIT	FOOT	465	465
X0322729	MATERIAL TRANSFER DEVICE	TON	52,501	52,501
* X0323014	ELECTRIC CABLE IN CONDUIT, CONOGA-30003	FOOT	840	840
* X0323015	PIEZO ELECTRIC AXLE SENSOR, CLASS II	FOOT	14	14
* X0325412	REMOVE AND REPLACE STEEL PLATE BEAM GUARDRAIL, SPECIAL	FOOT	850	850
X4066540	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N105	TON	12,340	12,340
X4066660	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0. N105	TON	40,161	40,161
* X6330115	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL, REMOVE AND RELOCATE	EACH	2	2
* X6330200	VERTICAL ADJUSTMENT OF TRAFFIC BARRIER TERMINAL	EACH	3	3
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	21	21
XX002870	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	SQ YD	17,915	17,915
Z0017202	DOWEL BARS, 1 1/2"	EACH	1,520	1,520
Z0075310	TIE BARS, 3/4"	EACH	30	30
25000350	SEEDING, CLASS 7	ACRE	1.25	1.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	198	198
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	148	148
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	148	148
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.5	2.5
25001010	SEEDING, CLASS 2 (MODIFIED)	ACRE	1.25	1.25
25100115	MULCH, METHOD 2	ACRE	2.5	2.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	247	247
28000300	TEMPORARY DITCH CHECKS	EACH	6	6
28102600	STONE RIPRAP DITCH	TON	880	880
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	32,176	32,176
40600105	BITUMINOUS MATERIALS (PRIME COAT), SPECIAL	GALLON	18,802	18,802
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	2,492	2,492
40600990	TEMPORARY RAMP	SQ YD	339	339
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	469	469
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	1,609	1,609
44000011	BITUMINOUS SURFACE REMOVAL 4"	SQ YD	106,898	106,898
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	4,814	4,814
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	600	600
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	19	19
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	80	80
44213100	PAVEMENT FABRIC	SQ YD	100	100

* SPECIALTY ITEM

PLOT DATE = 8/22/2006
 FILE NAME = c:\prowork\98948\98948.dwg
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = thomasr