

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	WILLIAMSON	55	13
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

\* CX1-(4,4-1,5,6,6-2) R-1

## TRAFFIC BARRIER SCHEDULE

LOCATION STATION TO STATION	GUARDRAIL REMOVAL FOOT	SPBGR TYPE A FOOT	VERT ADJ OF GR FOOT	REMOVE & REPLACE SPBGR, SPECIAL FOOT	TRAFFIC BARRIER TERMINAL					FURN & INSTALL GR BLOCKS EACH	GUARDRAIL MARKERS		TERMINAL MARKERS DIRECT APPLIED EACH	REMARKS
					TY 1, SPL (TAN) EACH	TY 1, REM & REL EACH	TYPE 5 EACH	TYPE 6B EACH	VERT ADJ EACH		AMBER EACH	SILVER EACH		
NORTHBOUND														
LT 25+16.00 TO 25+28.50			12.5											TERMINAL ADJUSTMENT
LT 25+28.50 TO 33+78.50				850.0								11		DAMAGED RAIL
LT 33+78.50 TO 34+28.50									1					TERMINAL ADJUSTMENT
LT 80+32.00 TO 80+44.50			12.5											TERMINAL ADJUSTMENT
LT 80+44.50 TO 82+06.25	161.8	100.0					1	1				2		DAMAGED RAIL / TERMINAL UPDATE
LT 82+06.25 TO 84+56.25	248.0	250.0										4		DAMAGED RAIL
LT 84+56.25 TO 85+06.25							1							RELOCATE TERMINAL
LT 166+25.00 TO 168+75.00		250.0										4		EXTEND SPBGR
LT 168+75.00 TO 169+25.00							1							RELOCATE TERMINAL
RT 182+22.00 TO 182+72.00	50.0					1							1	DAMAGED TERMINAL
LT 229+31.00 TO 232+15.00			284.0							50				VERTICAL ADJUSTMENT
LT 232+15.00 TO 232+65.00	50.0					1							1	DAMAGED TERMINAL
RT 229+07.00 TO 232+44.50	138.0	337.5									5			EXTEND SPBGR
RT 232+44.50 TO 232+94.50						1							1	TERMINAL UPDATE
LT 254+98.00 TO 255+44.25	46.3								1					TERMINAL UPDATE
LT 255+44.25 TO 258+26.00			232.0						1	41			1	VERTICAL ADJUSTMENT
LT 363+26.50 TO 363+71.25	44.8								1					TERMINAL UPDATE
LT 363+71.25 TO 366+62.50			242.0						1	43				VERTICAL ADJUSTMENT
<b>PROJECT TOTALS:</b>	<b>739</b>	<b>938</b>	<b>783</b>	<b>850</b>	<b>3</b>	<b>2</b>	<b>1</b>	<b>3</b>	<b>3</b>	<b>134</b>	<b>5</b>	<b>21</b>	<b>4</b>	
												26		

PLOT DATE = 8/18/2006  
 FILE NAME = 60100165.dwg  
 USER NAME = shepardjg