

SUMMARY OF QUANTITIES				CONSTRUCTION CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITY	100% STATE URBAN 0014
20200100	EARTH EXCAVATION	CU YD	378	378
3100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	737	737
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2
40600300	AGGREGATE (PRIME COAT)	TON	9	9
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	429	429
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	660	660
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	680	680
44213200	SAW CUTS	FOOT	814	814
48101200	AGGREGATE SHOULDERS, TYPE B	TON	48	48
50102400	CONCRETE REMOVAL	CU YD	145.0	145.0
50157300	PROTECTIVE SHIELD	SQ YD	5,024	5,024
50300225	CONCRETE STRUCTURES	CU YD	86.1	86.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	124.4	124.4
50300260	BRIDGE DECK GROOVING	SQ YD	3,350	3,350
50300300	PROTECTIVE COAT	SQ YD	3,570	3,570
5030550	PROTECTIVE COAT (SPECIAL)	SQ YD	1,286	1,286
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	31,060	31,060
52000110	PREFORMED JOINT STRIP SEAL	FOOT	175	175
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	41	41
52100520	ANCHOR BOLTS, 1"	EACH	82	82
58700300	CONCRETE SEALER	SQ FT	1,428	1,428
59000200	EPOXY CRACK INJECTION	FOOT	3	3
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	681	681
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	840	840
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	296	296
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3938	3938
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	40	40
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	60	60
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	126	126
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	110	110
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	8,030	8,030
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	410	410
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	45	45
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	50	50
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	18	18
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	45	45
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	18	18
Z0018010	DRAINAGE SCUPPERS, DS-33	EACH	12	12

SUMMARY OF QUANTITIES				CONSTRUCTION CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITY	100% STATE URBAN 0014
X0323359	WASHING AND CLEANING	L SUM	1	1
X0324126	GALVANIC ANODE	EACH	122	122
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	155	155
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	1,835	1,835
X0326444	SURFACE FILLER (SPECIAL)	GALLON	4	4
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	1
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	3,570	3,570
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	22	22
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	3,570	3,570
Z0010700	COLD MILLING	SQ YD	2591	2591
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	5	5
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	7	7
Z0018800	DRAINAGE SYSTEM	L SUM	1	1
Z0032300	JACKING EXISTING SUPERSTRUCTURE	L SUM	1	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	1	1
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	10	10

FILE NAME = 0264024-sht-300.dgn
 PLOT DATE = 8/12/2010
 PLOT SCALE = 50.0000' / IN.



DESIGNED - S.J.P.
 DRAWN - A.C.S.
 CHECKED - M.P.
 DATE - AUGUST 2010

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 IL. RTE. 251

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
740	(108HV) M	OGLE	55	3
CONTRACT NO. 64G24			FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT	