

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1346 & 2626	05-00050-00-CH	COOK/DUPAGE	94	4
SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-80031569				

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A			Y031-1F	Y030-1E
				DEVON AVE & N. ARLINGTON HEIGHTS RD (COOK COUNTY) 70% FEDERAL 30% LOCAL	S. ARLINGTON HEIGHTS RD (DUPAGE COUNTY) 70% FEDERAL 30% LOCAL	VILLAGE ITEMS 70% FEDERAL 30% LOCAL	TRAFFIC SIGNALS 70% FEDERAL 30% LOCAL	LIGHTING 70% FEDERAL 30% LOCAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	84	63	21			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	43	43				
20101000	TEMPORARY FENCE	FOOT	120	120				
● 20101100	TREE TRUNK PROTECTION	EACH	4	4				
X ● 20101200	TREE ROOT PRUNING	EACH	4	4				
● 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	4	4				
X 20200100	EARTH EXCAVATION	CU YD	3993	2875	1118			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3220	2477	743			
X 20400800	FURNISHED EXCAVATION	CU YD	531	452	79			
X 20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	3220	2477	743			
X 20800150	TRENCH BACKFILL	CU YD	261	233	28			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	9660	7431	2229			
● 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3615	3615				
● 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	730		730			
X 21300010	EXPLORATION TRENCH, SPECIAL	FOOT	1350	1000	250			100
● 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	54	45	9			
● 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	54	45	9			
● 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	54	45	9			
● 25200100	SODDING	SQ YD	3851	3615	236			
● 25200110	SODDING, SALT TOLERANT	SQ YD	494		494			
● 25200200	SUPPLEMENTAL WATERING	UNIT	100	75	25			
● 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	90	75	15			
28000510	INLET FILTERS	EACH	95	74	21			
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	9581	7352	2229			
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	3853	3165	688			
X 35301300	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	794	544	250			
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	328		328			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4220	3502	718			
40600300	AGGREGATE (PRIME COAT)	TON	43	35	8			
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	28	28				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				

X INDICATES SPECIAL PROVISION  
● INDICATES SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

DATE: 5/27/08  
DESIGNED BY: KRK  
CHECKED BY: DJK