

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1346 & 2626	05-00050-00-CH	COOK/DUPAGE	94	7
SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-8003(569)				

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A			Y031-1F	Y030-1E
				DEVON AVE & N. ARLINGTON HEIGHTS RD (COOK COUNTY)	S. ARLINGTON HEIGHTS RD (DUPAGE COUNTY)	VILLAGE ITEMS	TRAFFIC SIGNALS	LIGHTING
				70% FEDERAL 30% LOCAL	70% FEDERAL 30% LOCAL	70% FEDERAL 30% LOCAL	70% FEDERAL 30% LOCAL	70% FEDERAL 30% LOCAL
60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	6	6				
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3	3				
60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	2	2				
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2				
60500050	REMOVING CATCH BASINS	EACH	6	4	2			
60500060	REMOVING INLETS	EACH	19	15	4			
X 60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	2	1	1			
X 60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	6	5	1			
X 60500110	FILLING MANHOLES, SPECIAL	EACH	1	1				
X 60601005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	95	80	15			
X 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	316	179	137			
X 60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	20	20				
X 60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	56	56				
X 60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4469	3773	696			
X 60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	901	663	238			
X 60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	595		595			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	45		45			
X 60618400	CONCRETE MEDIAN, TYPE C-4	SQ FT	2973	2973				
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	2537	1527	1010			
60624600	CORRUGATED MEDIAN	SQ FT	10809	10702	107			
● 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	225	225				
● 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1				
X ● 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	1	1				
63200310	GUARDRAIL REMOVAL	FOOT	188	188				
● 66900200	NON SPECIAL WASTE DISPOSAL	CU YD	250	250				
● 66900450	SPECIAL WASTE PLANS AND REPORT	L. SUM	1	1				
● 66900510	BETX-PNAS SOIL ANALYSIS	EACH	3	3				
X ● 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	9	3			
● 67100100	MOBILIZATION	L. SUM	1	0.75	0.25			

X INDICATES SPECIAL PROVISION
● INDICATES SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

DATE: 5/27/08
DESIGNED BY: KRK
CHECKED BY: DJK