

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1346 & 2626	05-00050-00-CH	COOK/DUPAGE	94	8
SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-8003569				

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A			Y031-1F	Y030-1E
				DEVON AVE & N. ARLINGTON HEIGHTS RD (COOK COUNTY) 70% FEDERAL 30% LOCAL	S. ARLINGTON HEIGHTS RD (DUPAGE COUNTY) 70% FEDERAL 30% LOCAL	VILLAGE ITEMS 70% FEDERAL 30% LOCAL	TRAFFIC SIGNALS 70% FEDERAL 30% LOCAL	LIGHTING 70% FEDERAL 30% LOCAL
X 70101700	TRAFFIC CONTROL AND PROTECTION	L. SUM	1	0.75	0.25			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	9	3			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1477	1215	262			
70300510	PAVEMENT MARKING TAPE, TYPE III LETTER AND SYMBOLS	SQ FT	724	557	167			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	13428	11334	2094			
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	3142	2372	770			
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	702	702				
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	248	248				
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	546	400	146			
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	12887	10786	2101			
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	2236	1657	579			
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	354	354				
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	293	293				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	15009	12535	2474			
● 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	5	5				
● 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	2				
● 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	19	12	7			
● 72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	1	1			
● 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	573	394	179			
● 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	724	557	167			
● 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10948	9304	1644			
● 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3142	2372	770			
● 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	702	702				
● 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	248	248				
● 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	276	276				
● 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	98	98				
● 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	360	360				
● 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	18	18				
● 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	123	123				
X ● 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1				

X INDICATES SPECIAL PROVISION
● INDICATES SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE: 5/27/08
DESIGNED BY: KRK
CHECKED BY: DJK