

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1346 & 2626	05-00050-00-CH	COOK/DUPAGE	94	10
SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-80034569				

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A			Y031-1F	Y030-1E
				DEVON AVE & N. ARLINGTON HEIGHTS RD (COOK COUNTY) 70% FEDERAL 30% LOCAL	S. ARLINGTON HEIGHTS RD (DUPAGE COUNTY) 70% FEDERAL 30% LOCAL	VILLAGE ITEMS 70% FEDERAL 30% LOCAL	TRAFFIC SIGNALS 70% FEDERAL 30% LOCAL	LIGHTING 70% FEDERAL 30% LOCAL
X ● 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2925				2925	
X ● 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN NO. 14 1 PAIR	FOOT	6333				6333	
X ● 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	111				111	
X ● 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	4				4	
X ● 87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1				1	
X ● 87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1				1	
X ● 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	2				2	
X ● 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16				16	
X ● 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4				4	
X ● 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30				30	
X ● 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	30				30	
● 87900200	DRILL EXISTING HANDHOLE	EACH	1				1	
X ● 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4				4	
X ● 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	6				6	
X ● 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2				2	
X ● 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2				2	
X ● 88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	8				8	
X ● 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10				10	
X ● 88500100	INDUCTIVE LOOP DETECTOR	EACH	19				19	
X ● 88600100	DETECTOR LOOP, TYPE I	FOOT	1137				1137	
X ● 88700200	LIGHT DETECTOR	EACH	3				3	
X ● 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1				1	
X ● 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8				8	
X ● 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1				1	
X ● 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1				1	
X ● 89502380	REMOVE EXISTING HANDHOLE	EACH	13				13	
X ● 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9				9	
X Z0022800	FENCE REMOVAL	FOOT	123	123				
X Δ Z0076600	TRAINEES	HOURS	1000	1000				
X XX000613	MODULAR BLOCK RETAINING WALL	SQ FT	321	321				

X INDICATES SPECIAL PROVISION Δ Y080
● INDICATES SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

DATE: 5/27/08
DESIGNED BY: KRK
CHECKED BY: DJK