

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1346 & 2626	05-00050-00-CH	COOK/DUPAGE	94	15
SCHEDULE OF QUANTITIES				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-8003(569)				

SCHEDULE OF DRIVEWAYS			
STATION	DRIVEWAY REMOVAL (SQ YD)	PCC DRIVEWAY, 8 INCH, SPECIAL (SQ YD)	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 15 1/2" (SQ YD)
55+85, RT	37	36	
58+13, LT	37	50	
60+50, RT	112	52	
61+60, RT	307	42	
63+90, RT	44	37	
64+64, LT	65	34	
65+15, LT	61	51	
65+31, RT	38	33	
65+58, LT	57	28	
66+04, LT	36	23	
67+24, LT	35	41	
68+03, LT	55	70	
68+88, LT	30	31	
69+90, LT	61	72	
10+79, RT	38		28
11+58, RT	218	137	
12+54, RT	153	86	
14+00, LT	85	46	
14+50, RT	58		34
17+48, RT	42	43	
18+85, RT	44	28	
20+54, LT	92	71	
21+67, RT	23	38	
22+63, RT	68	59	

SCHEDULE OF TREE REMOVAL		
STATION	6 TO 15 UNIT DIAMETER	OVER 15 UNIT DIAMETER
60+96, RT	6	
61+12, RT	8	
14+46, LT	10	
14+59, LT	11	
18+19, RT	13	
19+74, LT		19
21+26, LT	12, 12	
21+81, LT	12	24

EARTHWORK SCHEDULE					
ITEM	UNIT	PRE-STAGE 1	STAGE 1	STAGE 2	STAGE 3
		EARTH EXCAVATION	C.Y.	28	3145
EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	C.Y.	24	2673	362	335
EMBANKMENT REQUIRED	C.Y.	0	380	6	145
EARTHWORK BALANCE					
WASTE (+) OR SHORTAGE (-)	C.Y.	+24	+2293	+356	+190

SHRINKAGE CALCULATED USING 15% SHRINKAGE FACTOR

A PAY ITEM FOR "FURNISHED EXCAVATION" HAS BEEN INCLUDED ON THE ASSUMPTION THAT, DUE TO LIMITED WORKING SPACE, ALL EMBANKMENT MAY HAVE TO BE BROUGHT IN FROM OUTSIDE THE PROJECT LIMITS.

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

DATE: 5/27/08
DESIGNED BY: KRK
CHECKED BY: DJK