

INDEX

- 1 COVER SHEET
- 2 INDEX, STANDARDS, SIGNATURES, & GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 PLAN & PROFILE VIEWS
- 5-7 TRAFFIC CONTROL DETAILS
- 8-29 BRIDGE DETAILS (FOR INFORMATION ONLY)

STANDARDS

- 701101-01
- 701106-01
- 701601-05
- 701701-05
- 701901
- BLR 21-7

CONTRACT: 72C04
SHEET 2 OF 29

GENERAL NOTES:

CLEANING AND PAINTING OF THE EXISTING STRUCTURAL STEEL SHALL BE AS SPECIFIED IN THE SPECIAL PROVISION FOR "CLEANING AND PAINTING EXISTING STEEL STRUCTURES."

IN SPANS 1 THRU 8 AND SPANS 12 THRU 19, ALL STRUCTURAL STEEL IN THESE SPANS SHALL BE COMPLETELY CLEANED AND PAINTED.

IN SPANS 9 THRU 11, THE ENTIRE EXTERIOR SURFACE AND BOTTOM OF THE BOTTOM FLANGE OF THE FASCIA BEAMS SHALL BE CLEANED AND PAINTED. IN ADDITION, ALL STRUCTURAL STEEL THAT COMPRISES THE CABLE ANCHORAGE SYSTEM THAT EXTENDS BELOW THE BOTTOM OF THE BEAMS AND THE STEEL PIPES THAT MAKE UP THE CABLE STAYED GUIDES, ABOVE THE DECK, SHALL ALSO BE CLEANED AND PAINTED. IN ADDITION, STRUCTURAL STEEL WITHIN 10 FEET (MEASURED ALONG THE BEAM) OF EITHER SIDE OF THE DECK JOINTS IN SPANS 9-11 SHALL BE CLEANED AND PAINTED .

ALL SURFACES DESIGNATED TO BE CLEANED AND PAINTED SHALL BE CLEANED PER NEAR WHITE METAL BLAST CLEANING SSPC-SP10 AND SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 - OZ/E/U.

THE COLOR OF THE FINAL FINISH COAT SHALL BE BLUE, MUNSELL NO. 10B 3/6.

THE SSPC-QP-1 AND SSPC-QP-2 PAINTING CONTRACTOR CERTIFICATIONS WILL BE REQUIRED FOR THIS PROJECT.

THE USE OF AIR MONITORS WILL BE REQUIRED.

COMMITMENTS:

AMEREN HAS INDICATED THEY WILL DEACTIVATE THE POWERLINES, ONE LOCATION AT A TIME, TO ALLOW PAINTING WORK TO BE PERFORMED. THE CONTRACTOR SHALL CONTACT AMEREN TO MAKE ARRANGEMENTS. SEE SPECIAL PROVISIONS FOR DETAILS.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6	
EXAMINED <u>July 15</u> 20 <u>08</u>	<u>[Signature]</u> ENGINEER OF OPERATIONS
EXAMINED <u>July 18</u> 20 <u>08</u>	<u>[Signature]</u> ENGINEER OF PROGRAM IMPLEMENTATION
EXAMINED <u>July 30</u> 20 <u>08</u>	<u>[Signature]</u> ENGINEER OF PROGRAM DEVELOPMENT

INDEX, NOTES, & SIGNATURES
FAP 63 (US 24)
SECTION BRIDGE PAINTING 2009
ADAMS COUNTY