

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		0004				
42101300	PROTECTIVE COAT	SO YD	40	40				
44000186	HOT-MIX ASPHALT SURFACE REMOVAL, 9"	SO YD	40	40				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	10	10				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2790	2790				
50800515	BAR SPLICERS	EACH	40	40				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1				
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6				
70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	FOOT	1220	1220				
70300924	PAVEMENT MARKING TAPE, TYPE IV 24"	FOOT	24	24				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1380	1380				
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	60	60				
X0326276	TEMPORARY LIGHTING FOR SINGLE LANE STAGING	L SUM	1	1				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		0004				
X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	SO FT	1440	1440				
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SO FT	1220	1220				
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	50.4	50.4				
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	1				

1

FILE NAME = USER NAME = rdh/jp DESIGNED - REVISIONS -  
 PLOT SCALE = 100,0000' / 1in. CHECKED - REVISIONS -  
 PLOT DATE = 8/22/2019 DATE - REVISIONS -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**US 14 OVER DITCH SO OAK GROVE ROAD  
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
066	2019-060-I	MCHENRY	18	3
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			CONTRACT NO. 62J37	

\*= SPECIALTY ITEM

REV. 10/28/19 REV. 9/30/19