SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE 0014 BRIDGE REPAIR 100% STATE		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	229	229		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	2044	2044		
50102400	CONCRETE REMOVAL	CU YD	11.1	11.1		
50157300	PROTECTIVE SHIELD	SQ YD	1132	1132		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	11.1	11.1		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1775	1775		
50800515	BAR SPLICERS	EACH	24	24		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	215.5	215.5		
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	2847	2847		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2	2		
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8	8		

* SPECIALTY ITEM

Rev.

FILE NAME : D264H73-sht-SOQ01.dgn
PLOT DATE : 8/6/2012
PLOT SCALE : 50.0000 ' / IN.

CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L./K.R.K.	REVISED -	
DRAWN -	K.R.K.	REVISED -	
CHECKED -	E.J.M.	REVISED -	
DATE -	FEBRUARY 2012	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
I-39 OVER I-88

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	D2 DECK REPAIR 2013-1	OGLE	32	3

CONTRACT NO. 64H73

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT