

SUMMARY OF QUANTITIES				LO1E	L1CE				LO1E	90% FEDERAL L1CE	10% STATE	LO1E				100% VILLAGE OF MORTON	
CODE	ITEM	UNIT	TOTAL QUANTITY	ROADWAY FAI 74 / FAI 155	I-155 OVER I-74 (RAMPS G & H)	I-74 OVER ABANDONED RAILROAD DEMOLITION	I-74 OVER JEFFERSON ST	I-74 OVER US 150 (JACKSON ST)	I-74 / I-155	MORTON AVE. OVER I-74	TRAFFIC SIGNALS	LIGHTING	SIGNING	LANDSCAPING	INTELLIGENT TRANSPORTATION SYSTEM	PINECREST DR PLANS	EMERGENCY VEHICLE PRE-EMPTION
				I-74 / I-155	SN 090-0165 (SB) SN 090-0166 (NB)	SN 090-0014 (WB) SN 090-0015 (EB)	SN 090-0167	SN 090-0169	OVERHEAD SIGN STRUCTURES	SN 090-0141							
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	27,244	27,244													
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SO YD	35,903	35,903													
42001300	PROTECTIVE COAT	SO YD	286,779	286,779													
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	4,987	4,987													
42100320	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 11"	SO YD	103,750	103,750													
42100615	PAVEMENT REINFORCEMENT	SO YD	103,750	103,750													
42101090	TRANSVERSE TERMINAL JOINT COMPLETE 24'	EACH	2	2													
42101436	LUG SYSTEM COMPLETE 36'	EACH	5	5													
42101447	LUG SYSTEM COMPLETE 47'	EACH	1	1													
44000100	PAVEMENT REMOVAL	SO YD	157,445	157,445													
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SO YD	1,263														1,263
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	470	470													
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	7,451	7,451													
44003100	MEDIAN REMOVAL	SO FT	34,533	33,852													681

* SPECIALTY ITEM

FILE NAME *	DESIGNED - EJA	REVISED -
...General\0468628\sh-500_04.dgn	DRAWN - TMB	REVISED -
USER NAME * preambille	CHECKED - JNR	REVISED -
PLOT DATE * 7/30/2012	DATE - JULY 20, 2012	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 4 OF 34 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
• 90-[14R]14HB-4,14,14HVBIBR		TAZEWELL	2435	11
CONTRACT NO. 68620			ILLINOIS FED. AID PROJECT	