

SIGN INDEX #	SIGN CODE	STA	OFFSET	DTL SHT #	ALIGNMENT	DIRECTION	EX OVRHD STR	EX STANDARD	EX SPECIAL	TEMP STD	TEMP SPCL	PROPOSED	DESCRIPTION	NEW STA.	NEW OFFSET	REMOVE SIGN PANEL ASSEMBLY TYPE A	REMOVE SIGN PANEL - TYPE 1	REMOVE GROUND MOUNTED SIGN SUPPORT	REMOVE CONCRETE FOUNDATIONS MOUNT	TEMPORARY SIGN PANEL ASSEMBLY	TEMPORARY SIGN PANEL OVERLAY	CONSTRUCT PROPOSED SIGN (SEE SIGN PLAN)	
																EACH	SQ FT	EACH	EACH	SQ FT	SQ FT		
12.02	D10-6	586+20.00	-87.40	-	I-74	WB		X					MILE MARKER 102	586+19.73	-91.40	1.00					RELOCATE		
12.03	E5-1A	580+45.00	48.00	-	I-74	EB		X					EXIT 102 A	582+00.00	42.40						RELOCATE		
14.01	W4-1R	606+43.19	70.86	-	I-74	EB		X					MERGE									16	
14.06	W13-3	204+52.40	21.50	-	MORTON RAMP B	-		X					RAMP SPEED 40 MPH									REMOVE	
21.03	W4-1L	13+16.00	65.88	-	I-155	SB		X					MERGE									REMOVE	
23.02	W4-1L	48+79.82	-72.76	-	I-155	NB		X					MERGE									REMOVE	
22.02	R2-I102	24+77.00	88.13	-	I-155	SB			X				SPEED LIMIT, TRUCKS TRAILERS 55				2	2					
4T.02		480+00.00	77.82	266	I-74	EB					X		I-155 USE RIGHT LANE									REMOVE	
4T.01		480+00.00	6.43	266	I-74	EB					X		I-74 USE LEFT LANE									REMOVE	
7.01	D9-I105	502+45.00	44.00	-	I-74	EB			X				EXIT 101 W/ ARROW	526+27.85	65.31							RELOCATE	
18.03	R3-I033	Store	Store	-	MORTON	NB			X				2 ARROWS AHEAD, 1 ARROW TURN ONLY	29+00.00	55.27						INSTALL FROM STORAGE		
17T.03		28+01.70	-0.26	272	MORTON	NB					X		LEFT LANE ARROW UP, RIGHT LANE UP/RIGHT									REMOVE	
17.03	R3-I031	28+00.00	-0.26	-	MORTON	NB			X				2 ARROWS AHEAD, 1 ARROW TURN									REMOVE	
18T.03		29+30.00	39.50	272	MORTON	NB					X		LEFT LANE ARROW UP, RT LANE UP/RT ONLY	29+30.00	41.51							RELOCATE	
18.17-1	M3-4	34+75.00	-0.77	-	MORTON	SB		X					CARDINAL DIRECTION - WEST	32+00.00	52.36	0.33						RELOCATE	
18.17-2	M1-1	34+75.00	-0.77	-	MORTON	SB		X					INTERSTATE ROUTE	32+00.00	52.36	0.33						RELOCATE	
18.17-3	M6-I037	34+75.00	-0.77	-	MORTON	SB			X				MERGE RIGHT	32+00.00	52.36	0.33						RELOCATE	
18T.02		-	-	272	MORTON	SB					X		LEFT LANE ARROW UP/LEFT ONLY, RIGHT LANE UP	33+20.00	-9.00							6	
19.05-1	R1-1	42+31.00	50.67	-	MORTON	NB		X					STOP SIGN				9						
19.07	R1-2	42+86.00	48.18	-	MORTON	NB		X					YIELD			1.00							
19.09	R1-2	43+16.00	74.39	-	MOTRON	NB		X					YIELD			1.00							
19.11	R1-1	9+51.39	2.36	-	MORTON RAMP B	-		X					STOP SIGN			1.00							
18.02-1	R1-1	31+25.00	-61.97	-	MORTON	SB		X					STOP SIGN				9						
PR19.13	W3-3			-	MORTON RAMP B	WB						X	TRAFFIC LIGHT AHEAD	PR	PR								X
TOTALS																5	18	2	2	6	16		

**TEMPORARY SIGN SCHEDULE**

FILE NAME = D468620-sh1-s1gn02-B-00.dgn	DESIGNED - HTL	REVISED -		<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>MAINTENANCE OF TRAFFIC PRE STAGE - SUB STAGE B - SIGN SCHEDULE</b>	F.A.I. RTE. *	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME = TERRA	DRAWN - KV	REVISED -				90-[14R;(14HB-4,14,14HVB)BR]	TAZEWELL	2433	85	
PLOT DATE = 7/18/2012	CHECKED - DA/LVA	REVISED -				CONTRACT NO. 68620				
	DATE - 7/20/2012	REVISED -	SCALE:	SHEET NO. 9 OF 85 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				