

LOCATION	ROAD	STATION FROM	STATION TO	AGGREGATE SUBGRADE IMPROVEMENT 8"	AGGREGATE SUBGRADE IMPROVEMENT 12"	STABILIZED SUBBASE HOT-MIX ASPHALT, 4"	AGGREGATE SHOULDERS, TYPE B 6"	PORTLAND CEMENT CONCRETE SHOULDERS 11"	PIPE UNDERDRAINS 4"	TEMPORARY PAVEMENT REMOVAL	AGGREGATE SHOULDER REMOVAL	WHITEWASHING FOR CONCRETE PAVEMENT	TEMPORARY PAVEMENT	GLARE SCREEN (NEW LOCATION)	GLARE SCREEN TO REMAIN	GLARE SCREEN TOTAL	TEMPORARY CONCRETE BARRIER (NEW LOCATION)	TEMPORARY CONCRETE BARRIER TO REMAIN	TEMPORARY CONCRETE BARRIER TOTAL	
				SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	CU YD	SQ YD	SQ YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
I-474	-	456+00.00	471+00.00	0	0	0	0	0	0	0	0	0	0	0	0	11203	0.0	0.0	31212.5	
I-74	456+00.00	471+00.00	486+00.00	0	0	0	0	0	0	0	0	0	0	391	0	0	312.5	1325.0		
I-74	471+00.00	486+00.00	501+00.00	0	0	0	0	0	0	1569	48	0	0	1500	0	GLARE SCREEN FROM PREVIOUS STAGE	1562.5	1500.0	TEMPORARY CONCRETE BARRIER FROM PREVIOUS STAGE	
I-74	486+00.00	501+00.00	516+00.00	0	0	0	0	0	0	1699	56	0	0	1500	0	0	2600.0	1500.0		
I-74	501+00.00	516+00.00	531+00.00	0	0	0	0	0	0	1155	37	0	0	2025	0	0	3525.0	1500.0		
I-74	516+00.00	531+00.00	546+00.00	4431	0	0	216	0	0	0	0	0	4431	1495	0	0	1537.5	1475.0		
RAMP G/H	118+50.00	101+47.00	531+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0		
I-74	531+00.00	546+00.00	561+00.00	2674	0	0	206	0	0	0	0	0	2674	871	0	0	875.0	1050.0		
I-74	546+00.00	561+00.00	576+00.00	0	0	0	0	0	0	452	17	0	0	1514	0	FOOT	2300.0	1275.0		
I-74	561+00.00	576+00.00	591+00.00	0	0	0	0	0	0	1176	44	0	0	1506	0	0	2125.0	950.0		
I-74	576+00.00	591+00.00	606+00.00	0	0	0	0	0	0	1012	48	0	0	401	0	0	1525.0	1400.0		
I-74	591+00.00	606+00.00	621+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	937.5	1200.0		
I-74	606+00.00	621+00.00	636+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	RELOCATE TEMPORARY CONCRETE BARRIER	
I-74	621+00.00	636+00.00	640+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0		
I-74	636+00.00	640+00.00	09+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0		
I-155	00+00.00	09+00.00	23+00.00	4009	0	0	234	0	0	535	16	0	4009	0	0	RELOCATE MODULAR GLARE SCREEN SYSTEM	650.0	0.0		
I-155	09+00.00	23+00.00	37+50.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	FOOT	
I-155	23+00.00	37+50.00	51+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0		
I-155	37+50.00	51+00.00	66+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	18037.5	
I-155	51+00.00	66+00.00	28+25.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	TEMPORARY CONCRETE BARRIER	
Morton Ave.	16+00.00	28+25.00	36+50.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0		
Morton Ave.	28+25.00	36+50.00	44+75.00	0	0	0	0	0	0	0	0	0	0	0	0	0	87.5	0.0		
Morton Ave.	36+50.00	44+75.00	58+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0		
Morton Ave.	44+75.00	58+00.00	TOTALS	11114	0	0	656	0	0	7598	266	0	11246	TOTALS	11203	0	11203	18037.5	13175.0	FOOT 0.0

LOCATION	ROAD	STATION FROM	STATION TO	PAVEMENT MARKING TAPE, TY III LETTERS & SYMBOLS	PAVEMENT MARKING TAPE, TYPE III 4"	PAVEMENT MARKING TAPE, TYPE III 8"	PAVEMENT MARKING TAPE, TYPE III 12"	PAVEMENT MARKING TAPE, TYPE III 24"	WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE II LINE 4"	POLYUREA PAVEMENT MARKING TYPE II LINE 8"	POLYUREA PAVEMENT MARKING TYPE II LINE 12"
				SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT
I-474	-	456+00.00	471+00.00	0	0	0	0	0	0	0	0	0
I-74	456+00.00	471+00.00	486+00.00	0	980	654	0	0	260	0	0	0
I-74	471+00.00	486+00.00	501+00.00	0	5750	250	0	0	200	0	0	0
I-74	486+00.00	501+00.00	516+00.00	0	6000	0	0	0	0	0	0	0
I-74	501+00.00	516+00.00	531+00.00	0	2900	0	0	0	0	3100	0	0
I-74	516+00.00	531+00.00	546+00.00	0	0	0	0	0	1188	5476	1792	0
RAMP G/H	118+50.00	101+47.00	531+00.00	0	0	0	0	0	0	0	0	0
I-74	531+00.00	546+00.00	561+00.00	0	0	0	0	0	1632	4538	0	0
I-74	546+00.00	561+00.00	576+00.00	0	1350	0	0	0	805	3599	378	0
I-74	561+00.00	576+00.00	591+00.00	0	4074	0	0	0	0	0	0	0
I-74	576+00.00	591+00.00	606+00.00	0	1124	0	0	0	1522	4216	568	0
I-74	591+00.00	606+00.00	621+00.00	0	367	0	0	0	1414	3623	568	0
I-74	606+00.00	621+00.00	636+00.00	0	1137	0	0	0	1408	2021	893	0
I-74	621+00.00	636+00.00	640+00.00	0	287	0	0	0	330	240	0	0
I-74	636+00.00	640+00.00	09+00.00	0	0	0	0	0	0	0	0	0
I-155	00+00.00	09+00.00	23+00.00	0	0	0	0	0	1225	3382	544	0
I-155	09+00.00	23+00.00	37+50.00	0	356	0	0	0	1212	3460	0	0
I-155	23+00.00	37+50.00	51+00.00	0	1272	0	0	0	593	0	0	0
I-155	37+50.00	51+00.00	66+00.00	0	0	0	0	0	0	0	0	0
I-155	51+00.00	66+00.00	28+25.00	0	0	0	0	0	0	0	0	0
Morton Ave.	16+00.00	28+25.00	36+50.00	35	2967	0	265	7	1367	0	0	0
Morton Ave.	28+25.00	36+50.00	44+75.00	53	5930	219	826	72	2064	0	0	0
Morton Ave.	36+50.00	44+75.00	58+00.00	0	5651	238	1214	3	1274	0	0	0
Morton Ave.	44+75.00	58+00.00	TOTALS	132	44469	1814	2854	82	17653	33655	4742	0

SHORT TERM PAVEMENT MARKING	CHANGEABLE MESSAGE SIGN
FOOT	CAL MO
TOTAL STAGE 2A	4,382 20.00

ATTENUATOR LOCATION SCHEDULE				IMPACT ATTENUATORS WIDE NEW OR RELOCATED EACH	IMPACT ATTENUATORS WIDE TO REMAIN EACH	IMPACT ATTENUATORS NARROW NEW OR RELOCATED EACH	IMPACT ATTENUATORS NARROW TO REMAIN EACH
ROAD	STATION	OFFSET	TYPE				
I-74	542+37.99	50.89	WIDE	1	0	0	0
I-74	470+84.21	55.47	WIDE	1	0	0	0
I-74	472+34.62	-24.72	WIDE	1	0	0	0
I-74	472+97.89	0.3	WIDE	1	0	0	0
I-74	553+08.91	43.58	WIDE	1	0	0	0
I-74	459+50.81	34.85	WIDE	1	0	0	0
I-74	548+52.53	22.53	WIDE	1	0	0	0
I-74	605+25.29	-16.25	NARROW	0	1	0	0
I-74	593+27.29	0.03	WIDE	1	0	0	0
I-155	13+94.78	82.75	WIDE	1	0	0	0
MORTON	42+22.04	-63.88	WIDE	1	0	0	0

	TEST LEVEL 2 ATTENUATORS NEW OR RELOCATED	TEST LEVEL 2 ATTENUATORS TO REMAIN	ATTENUATORS FROM PREVIOUS STAGE	IMPACT ATTENUATORS TEMPORARY (NON-REDUCTIVE), TEST LVL 2	IMPACT ATTENUATORS, TEMPORARY (FULLY REDUCTIVE, NARROW TEST LVL 2)	IMPACT ATTENUATORS, RELOCATE (FULLY REDUCTIVE, TEST LVL 2)	IMPACT ATTENUATORS, RELOCATE (NON-REDUCTIVE), TEST LVL 2
WIDE	1	0	3	0	-	-	1
NARROW	0	0	0	-	0	0	-

	TEST LEVEL 3 ATTENUATORS NEW OR RELOCATED	TEST LEVEL 3 ATTENUATORS TO REMAIN	ATTENUATORS FROM PREVIOUS STAGE	IMPACT ATTENUATORS TEMPORARY (NON-REDUCTIVE), TEST LVL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY REDUCTIVE, NARROW TEST LVL 3)	IMPACT ATTENUATORS, RELOCATE (FULLY REDUCTIVE, TEST LVL 3)	IMPACT ATTENUATORS, RELOCATE (NON-REDUCTIVE), TEST LVL 3
WIDE	8	1	2	7	-	-	1
NARROW	1	0	2	-	1	0	-