

LOCATION			AGGREGATE SUBGRADE IMPROVEMENT 8"	AGGREGATE SUBGRADE IMPROVEMENT 12"	STABILIZED SUBBASE HOT-MIX ASPHALT, 4"	AGGREGATE SHOULDERS, TYPE B 6"	PORTLAND CEMENT CONCRETE SHOULDERS 11"	PIPE UNDERDRAINS 4"	TEMPORARY PAVEMENT REMOVAL	AGGREGATE SHOULDER REMOVAL	WHITEWASHING FOR CONCRETE PAVEMENT	TEMPORARY PAVEMENT	GLARE SCREEN (NEW LOCATION)	GLARE SCREEN TO REMAIN	GLARE SCREEN ON-SITE	TEMPORARY CONCRETE BARRIER (NEW LOCATION)	TEMPORARY CONCRETE BARRIER TO REMAIN	TEMPORARY CONCRETE BARRIER ON-SITE	
ROAD	STATION FROM	STATION TO	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	CU YD	SQ YD	SQ YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
I-474	-	456+00.00	0	0	0	0	0	0	0	0	0	0	0	0	8709	0.0	0.0	16787.5	
I-74	456+00.00	471+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	637.5		
I-74	471+00.00	486+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	200.0		
I-74	486+00.00	501+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	112.5	987.5	TEMPORARY CONCRETE BARRIER FROM PREVIOUS STAGE	
I-74	501+00.00	516+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	912.5	587.5		
I-74	516+00.00	531+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	1087.5	1112.5		
RAMP G/H	118+50.00	101+47.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0		
I-74	531+00.00	546+00.00	0	0	0	0	0	0	1205	24	0	0	0	0	0	1575.0	0.0		
I-74	546+00.00	561+00.00	0	0	0	0	0	0	67	0	0	0	0	0	0	600.0	900.0		
I-74	561+00.00	576+00.00	0	0	0	0	0	0	0	0	0	0	0	1500	0.0	1500.0	FOOT		
I-74	576+00.00	591+00.00	0	0	0	0	0	0	0	0	0	0	0	1500	0.0	2225.0	17950.0		
I-74	591+00.00	606+00.00	0	0	0	0	0	0	0	0	0	0	0	304	0.0	1162.5			
I-74	606+00.00	621+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	RELOCATE TEMPORARY CONCRETE BARRIER		
I-74	621+00.00	636+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0			
I-74	636+00.00	640+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0			
I-155	00+00.00	09+00.00	0	0	0	0	0	0	3032	138	0	0	0	0	0	900.0	0.0		
I-155	09+00.00	23+00.00	0	0	0	0	0	0	1206	69	0	0	0	0	0	1462.5	0.0		
I-155	23+00.00	37+50.00	0	0	0	0	0	0	0	0	0	0	0	0	0	12.5	0.0	FOOT	
I-155	37+50.00	51+00.00	0	0	0	0	0	0	0	0	0	0	0	0	4506	0.0	0.0	6662.5	
I-155	51+00.00	66+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0		
Morton Ave.	16+00.00	28+25.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	TEMPORARY CONCRETE BARRIER	
Morton Ave.	28+25.00	36+50.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	437.5		
Morton Ave.	36+50.00	44+75.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	375.0		
Morton Ave.	44+75.00	58+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0		
TOTALS			0	0	0	0	0	0	5509	231	0	0	TOTALS	4506	4204	0	6662.5	10125.0	0.0

LOCATION			PAVEMENT MARKING TAPE, TY III LETTERS & SYMBOLS	PAVEMENT MARKING TAPE, TYPE III 4"	PAVEMENT MARKING TAPE, TYPE III 8"	PAVEMENT MARKING TAPE, TYPE III 12"	PAVEMENT MARKING TAPE, TYPE III 24"	WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE II LINE 4"	POLYUREA PAVEMENT MARKING TYPE II LINE 8"	POLYUREA PAVEMENT MARKING TYPE II LINE 12"
ROAD	STATION FROM	STATION TO	SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT
I-474	-	456+00.00	0	0	0	0	0	0	0	0	0
I-74	456+00.00	471+00.00	0	0	0	0	0	0	0	0	0
I-74	471+00.00	486+00.00	0	0	0	0	0	0	0	0	0
I-74	486+00.00	501+00.00	0	1148	0	0	265	0	0	0	0
I-74	501+00.00	516+00.00	0	7833	735	0	3330	0	0	0	0
I-74	516+00.00	531+00.00	0	899	181	0	2608	5657	949	0	0
RAMP G/H	118+50.00	101+47.00	0	0	0	0	0	0	0	0	0
I-74	531+00.00	546+00.00	0	755	0	0	2498	7077	0	0	0
I-74	546+00.00	561+00.00	0	3460	1733	0	2175	2868	0	0	0
I-74	561+00.00	576+00.00	0	159	0	0	169	0	0	0	0
I-74	576+00.00	591+00.00	0	0	0	0	0	0	0	0	0
I-74	591+00.00	606+00.00	0	0	0	0	0	0	0	0	0
I-74	606+00.00	621+00.00	0	0	0	0	0	0	0	0	0
I-74	621+00.00	636+00.00	0	0	0	0	0	0	0	0	0
I-74	636+00.00	640+00.00	0	0	0	0	0	0	0	0	0
I-155	00+00.00	09+00.00	0	2879	0	0	51	0	0	0	0
I-155	09+00.00	23+00.00	0	2944	0	0	114	0	0	0	0
I-155	23+00.00	37+50.00	0	1318	0	0	438	0	0	0	0
I-155	37+50.00	51+00.00	0	0	0	0	0	0	0	0	0
I-155	51+00.00	66+00.00	0	0	0	0	0	0	0	0	0
Morton Ave.	16+00.00	28+25.00	0	0	0	0	0	0	0	0	0
Morton Ave.	28+25.00	36+50.00	0	0	0	0	0	0	0	0	0
Morton Ave.	36+50.00	44+75.00	0	0	0	0	0	0	0	0	0
Morton Ave.	44+75.00	58+00.00	0	0	0	0	0	0	0	0	0
TOTALS			0	21395	2648	0	0	11647	15602	949	0

	SHORT TERM PAVEMENT MARKING	CHANGEABLE MESSAGE SIGN
	FOOT	CAL MO
TOTAL STAGE 8	2,030	27.00

ATTENUATOR LOCATION SCHEDULE				IMPACT ATTENUATORS WIDE NEW OR RELOCATED EACH	IMPACT ATTENUATORS WIDE TO REMAIN EACH	IMPACT ATTENUATORS NARROW NEW OR RELOCATED EACH	IMPACT ATTENUATORS NARROW TO REMAIN EACH
ROAD	STATION	OFFSET	TYPE				
I-74	525+95.21	120.59	WIDE		1	0	0
I-74	603+86.03	-5.37	WIDE		1	0	0
I-74	464+05.09	1.01	WIDE		1	0	0
I-74	576+72.17	43.99	NARROW		0	0	1
I-155	12+13.35	-65.99	WIDE	1	0	0	0
I-155	34+40.81	-40.15	WIDE	1	0	0	0
MORTON	32+13.30	42.84	WIDE		1	0	0

	TEST LEVEL 2 ATTENUATORS NEW OR RELOCATED	TEST LEVEL 2 ATTENUATORS TO REMAIN	ATTENUATORS FROM PREVIOUS STAGE	IMPACT ATTENUATORS TEMPORARY (NON-REDUCTIVE), TEST LVL 2	IMPACT ATTENUATORS, TEMPORARY (FULLY REDUCTIVE, NARROW TEST LVL 2)	IMPACT ATTENUATORS, RELOCATE (FULLY REDUCTIVE, TEST LVL 2)	IMPACT ATTENUATORS, RELOCATE (NON-REDUCTIVE), TEST LVL 2
WIDE	0	1	1	0	-	-	0
NARROW	0	0	0	-	0	0	-

	TEST LEVEL 3 ATTENUATORS NEW OR RELOCATED	TEST LEVEL 3 ATTENUATORS TO REMAIN	ATTENUATORS FROM PREVIOUS STAGE	IMPACT ATTENUATORS TEMPORARY (NON-REDUCTIVE), TEST LVL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY REDUCTIVE, NARROW TEST LVL 3)	IMPACT ATTENUATORS, RELOCATE (FULLY REDUCTIVE, TEST LVL 3)	IMPACT ATTENUATORS, RELOCATE (NON-REDUCTIVE), TEST LVL 3
WIDE	2	3	6	0	-	-	2
NARROW	0	1	2	-	0	0	-

FILE NAME =	DESIGNED - HTL	REVISED -
D468620-sh1-schedule-08.dgn	DRAWN - KV	REVISED -
USER NAME = TERRA	CHECKED - DA/LVA	REVISED -
PLOT DATE = 7/29/2012	DATE - 7/20/2012	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
STAGE 8 SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 53 OF 85 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	90-[14R(14HB-4,14,14HB)BR]	TAZEWELL	2433	129
CONTRACT NO. 68620				
ILLINOIS FED. AID PROJECT				