

PAVEMENT MARKING SCHEDULE								
LOCATION		78000200	78000500	78000600	78004210	78006100	78006140	78006180
		THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 8"	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 24"
BEGIN STATION	END STATION	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT
ADAMS STREET								
PERSIMMON TO MAPLE								
140+10.00	145+93.90	289	1186	0	120	56	447	39
MAPLE TO ELM								
145+93.90	150+13.90	0	373	0	100	25	194	22
ELM TO OAK								
150+13.90	154+41.40	0	418	0	100	35	188	45
OAK TO STATE								
154+41.40	158+74.80	0	511	0	90	25	280	51
STATE TO WALNUT								
158+74.80	165+30.00	20	722	0	140	77	381	34
WALNUT TO WILLIAM KUMPF								
165+30.00	166+72.83	70	339	0	0	31	49	20
JEFFERSON AVENUE								
PERSIMMON TO MAPLE								
240+25.00	245+80.80	0	1062	0	140	25	368	33
MAPLE TO ELM								
245+80.80	250+10.80	0	1138	0	100	25	221	27
ELM TO OAK								
250+10.80	255+55.00	0	965	0	110	67	470	87
OAK TO WILLIAM KUMPF								
255+55.00	267+95.74	360	2534	258	0	82	168	28
PERSIMMON STREET								
JEFFERSON TO ADAMS								
593+60.00	596+70.00	584	202	0	0	21	0	0
ADAMS TO WASHINGTON								
598+25.00	599+74.71	299	160	0	0	0	0	0
MAPLE STREET								
JEFFERSON TO ADAMS								
246+60.00	249+55.00	554	129	0	0	0	0	0
ADAMS TO WASHINGTON								
698+10.00	701+54.14	688	0	0	0	0	0	0
OAK STREET								
JEFFERSON TO ADAMS								
793+65.00	796+60.00	677	21	0	0	78	0	0
ADAMS TO WASHINGTON								
796+15.00	799+90.53	351	0	0	0	0	0	0
STATE STREET								
ADAMS TO WASHINGTON								
898+45.00	901+00.45	536	126	23	0	0	0	35
WASHINGTON TO COMMERCIAL								
903+15.00	907+05.86	798	195	19	0	0	117	24
ELM STREET								
746+15.00	747+08.00	554	129	0	0	0	0	0
WALNUT STREET								
950+34.30	952+00.00	544	233	0	0	5	0	0
COMMERCIAL STREET								
1711+50.00	1716+60.00	789	1217	0	0	23	166	38
TOTAL		7113	11660	300	900	576	3039	483

CURB SCHEDULE						
LOCATION		60600605	60603800	60605000	60608300	X6060003
		CONCRETE CURB, TYPE B	COMBINATION CONCRETE CURB AND GUTTER, TYPE B 6.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE B 6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.18
BEGIN STATION	END STATION	FOOT	FOOT	FOOT	FOOT	FOOT
ADAMS STREET						
PERSIMMON TO MAPLE						
140+10.00	145+93.90	104	1106	0	0	0
MAPLE TO ELM						
145+93.90	150+13.90	61	870	0	0	0
ELM TO OAK						
150+13.90	154+41.40	8	866	0	0	0
OAK TO STATE						
154+41.40	158+74.80	36	898	0	0	0
STATE TO WALNUT						
158+74.80	165+30.00	44	1265	0	0	0
JEFFERSON AVENUE						
PERSIMMON TO MAPLE						
240+25.00	245+80.80	103	1230	0	0	0
MAPLE TO ELM						
245+80.80	250+10.80	55	942	0	0	0
ELM TO OAK						
250+10.80	255+55.00	16	951	82	0	0
PERSIMMON STREET						
JEFFERSON TO ADAMS						
593+60.00	596+70.00	63	638	0	0	0
ADAMS TO WASHINGTON						
598+25.00	599+74.71	111	316	0	0	0
MAPLE STREET						
JEFFERSON TO ADAMS						
246+60.00	249+55.00	0	310	0	0	0
ADAMS TO WASHINGTON						
698+10.00	701+54.14	480	654	0	0	0
OAK STREET						
JEFFERSON TO ADAMS						
793+65.00	796+60.00	25	577	0	0	0
ADAMS TO WASHINGTON						
796+15.00	799+90.53	48	298	0	0	0
STATE STREET						
ADAMS TO WASHINGTON						
898+45.00	901+00.45	152	545	0	0	0
WASHINGTON TO COMMERCIAL						
903+15.00	907+05.86	52	730	0	0	0
ELM STREET						
746+15.00	747+08.00	0	308	0	290	0
WALNUT STREET						
950+34.30	952+00.00	0	476	0	136	0
COMMERCIAL STREET						
1711+50.00	1716+60.00	243	898	0	573	977
TOTAL		1601	13878	82	999	977

SIDEWALK SPECIAL SCHEDULE			
LOCATION		50901780	X006429
		PIPE HANDRAIL	SIDEWALK, SPECIAL
BEGIN STATION	END STATION	FOOT	SQ YD
ADAMS STREET			
MAPLE TO ELM			
145+93.90	150+13.90	44.5	216
OAK TO STATE			
154+41.40	158+74.80	44.5	225
TOTAL		89	441