

**SUMMARY OF QUANTITIES (CONT'D)**

LOCATION OF WORK:	ROADWAY	ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	INTERCONNECT	NEW SIDWALK
FUNDING BREAKOUT:	4 TRAFFIC LANES	LIGHTING	IOWA ST. AND	INDIANA AVE AND	OREGON ST	US 136	US 136
CONSTRUCTION TYPE CODE:	WIDENING AND	NON-	WEST V. A.	WEST DACC ENT.	INTERSECTION		
	RESURFACING	PARTICIPATING	ENTRANCE	INTERSECTION			
	STA 93+951.420	STA. 93+951.420 TO	INTERSECTION				
	TO STA 95+484.880	STA. 95+484.880	80% FEDERAL	80% FEDERAL	80% FEDERAL	80% FEDERAL	80% STATE
	80% FEDERAL	10% STATE	10% STATE	10% STATE	10% STATE	10% STATE	80% STATE
	20% STATE	100% DANVILLE	10% DANVILLE	10% DANVILLE	10% DANVILLE	10% DANVILLE	20% DANVILLE
	0004	0021	0021	0021	0021	0021	0021

<u>CODE NO.</u>	<u>ITEM DESCRIPTION</u>	<u>UNIT</u>	<u>URBAN TOTAL QUANTITY</u>	<u>QUANTITY</u>	<u>QUANTITY</u>	<u>QUANTITY</u>	<u>QUANTITY</u>	<u>QUANTITY</u>	<u>QUANTITY</u>
					<u>07POL</u>				<u>07COL</u>

*MX030457	STORM SEWER (WATER MAIN REQUIREMENTS) TYPE 1, 375MM	METER	2.5	2.5					
*MX030581	STORM SEWER (WATER MAIN REQUIREMENTS) TYPE 2, 600MM	METER	56.5	56.5					
*MX030582	STORM SEWER (WATER MAIN REQUIREMENTS) TYPE 2, 750MM	METER	42.5	42.5					
<del>MX032200</del>	<del>ENGINEERED BARRIER</del>	<del>CU M</del>							
MX033840	VANE DRAINS	METER	62.0	62.0					
MX033841	FENCE REMOVAL AND REERECTION	METER	166.4	166.4					
MX033842	PARTIAL DEPTH REMOVAL, 75MM	SO M	296.0	296.0					
MX033843	PARTIAL DEPTH PATCHING	M TON	53.0	53.0					
MX033844	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N90	M TON	7431.0	7431.0					
MX033845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-9.5 FG, N90	M TON	2852.0	2852.0					
MX501020	CONCRETE RETAINING WALL REMOVAL, VARIABLE HEIGHT	CU M	1.3	1.3					
MX606110	CONCRETE CURB, TYPE B (SPECIAL)	METER	174.3	174.3					
*MX871055	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	METER	976.0					976.0	
MZ013300	CONCRETE REMOVAL (SPECIAL)	SO M	13.0	13.0					

\* SPECIALTY ITEM

8/17/2012

c:\pw\work\pwidot\ceor lock\jd\0313241\090939-sht-500.dgn