

CUT AND FILL TABLE

STATION	CUT	FILL	STATION	CUT	FILL	STATION	CUT	FILL	STATION	CUT	FILL	STATION	CUT	FILL
FRANKLIN CO.	SQ FT	SQ FT	FRANKLIN CO.	SQ FT	SQ FT	WILLIAMSON CO.	SQ FT	SQ FT	WILLIAMSON CO.	SQ FT	SQ FT	WILLIAMSON CO.	SQ FT	SQ FT
236+00	9	0	284+00	38	23	41+00	39	26	89+00	21	40	137+00	33	23
237+00	10	0	285+00	33	28	42+00	38	30	90+00	23	33	138+00	29	28
238+00	12	0	286+00	36	29	43+00	36	31	91+00	23	40	139+00	33	23
239+00	13	0	287+00	30	38	44+00	33	23	92+00	23	41	140+00	35	19
240+00	29	32	288+00	36	30	45+00	23	43	93+00	21	48	141+00	34	23
241+00	24	51	289+00	40	37	46+00	23	44	94+00	24	65	142+00	35	22
242+00	29	55	WILLIAMSON CO.			46+98	26	37	95+00	23	43	143+00	18	51
243+00	33	43	0+02.25	33	34	48+00	23	38	96+00	23	40	144+00	26	49
244+00	29	45	1+00	30	34	49+00	24	38	97+00	20	36	145+00	24	31
245+00	27	52	2+00	20	39	50+00	26	37	98+00	28	33	146+00	30	17
246+00	25	45	3+00	21	43	51+00	29	30	99+00	28	32	147+00	34	13
247+00	25	42	4+00	29	33	52+00	30	25	100+00	30	29	148+00	42	8
248+00	27	38	5+00	27	33	53+00	23	38	101+00	32	22	149+00	33	16
249+00	27	36	6+00	24	37	54+00	21	48	102+00	28	28	150+00	33	17
250+00	26	37	7+00	23	39	55+00	17	66	103+00	23	38	151+00	33	20
251+00	27	36	8+00	88	0	56+00	16	88	104+00	28	31	152+00	30	30
252+00	22	49	9+00	34	19	57+00	19	66	105+00	28	33	153+00	30	31
253+00	22	47	10+00	38	18	58+00	18	62	106+00	26	27	154+00	14	80
254+00	24	43	11+00	37	18	59+00	19	78	107+00	38	22	155+00	31	27
255+00	26	45	12+00	30	24	60+00	20	50	108+00	31	25	156+00	25	27
256+00	33	32	13+00	38	18	61+00	24	42	109+00	32	24	157+00	23	30
257+00	33	31	14+00	33	24	62+00	24	40	110+00	31	28	158+00	17	48
258+00	33	29	15+00	35	22	63+00	21	48	111+00	29	32	159+00	19	37
259+00	28	36	16+00	27	26	64+00	25	47	112+00	22	39	160+00	21	39
260+00	32	33	17+00	24	25	65+00	21	77	113+00	20	42	161+00	27	47
261+00	35	28	18+00	24	25	66+00	25	46	114+00	21	37	162+00	20	68
262+00	29	26	19+00	23	28	67+00	21	50	115+00	22	31	163+00	18	71
263+00	30	31	20+00	23	35	68+00	21	46	116+00	27	26	164+00	31	41
264+00	29	30	21+00	23	38	69+00	19	52	117+00	31	27	165+00	50	7
265+00	36	24	22+00	26	33	70+00	23	48	118+00	32	26	166+00	41	7
266+00	30	30	23+00	26	35	71+00	19	81	119+00	35	23	167+00	45	5
267+00	25	37	24+00	24	38	72+00	22	49	120+00	30	30	168+00	21	8
268+00	30	32	25+00	29	33	73+00	21	45	121+00	31	24	169+00	19	4
269+00	32	30	26+00	24	130	74+00	21	41	122+00	37	18	170+00	12	0
270+00	37	14	27+00	18	110	75+00	20	40	123+00	27	32	171+00	9	0
271+00	30	30	28+00	17	102	76+00	27	37	124+00	30	31			
272+00	26	32	29+00	18	103	77+00	28	40	125+00	26	47			
273+00	31	28	30+00	17	110	78+00	24	47	126+00	25	35			
274+00	29	35	31+00	35	88	79+00	22	52	127+00	29	29			
275+00	28	39	32+00	56	67	80+00	23	57	128+00	33	26			
276+00	24	43	33+00	53	31	81+00	35	33	129+00	28	28			
277+00	24	50	34+00	54	17	82+00	39	18	130+00	31	26			
278+00	22	56	35+00	47	18	83+00	26	30	131+00	29	29			
279+00	24	48	36+00	46	26	84+00	22	46	132+00	30	28			
280+00	30	44	37+00	41	38	85+00	21	50	133+00	23	55			
281+00	30	40	38+00	45	23	86+00	22	62	134+00	33	39			
282+00	30	37	39+00	44	21	87+00	23	46	135+00	60	8			
283+00	32	31	40+00	44	23	88+00	20	44	136+00	15	0			

REVISÉD SHEET 10-22-2018

MODEL: Default
FILE NAME: P:\110448\BID\INTEG_illinois.gov_PWD\DOT\Documents\DOT_Official\District_9\Project\178363\CADD\at\CD\sheet\015_031_029\178363-sch-schedule.dgn

USER NAME = rollavr	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 10/12/2018	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE	
SCALE:	SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	**	*	191	19
CONTRACT NO. 78363				
ILLINOIS FED. AID PROJECT				

**(X-4)R-2;(28-5-1,28-5)R-1 *FRANKLIN / WILLIAMSON

PAVEMENT AND SHOULDER REMOVAL

STATION	STATION	LOCATION	PAVEMENT REMOVAL SQ YD	HOT MIX ASPHALT SURFACE REMOVAL 2" SQ YD	PAVED SHOULDER REMOVAL SQ YD
FRANKLIN CO.					
NORTHBOUND					
242+00.00	289+22.60	INSIDE SHLD			3,148
236+35.00	241+80.00	OUTSIDE SHLD			606
248+00.00	289+22.60	EXISTING LANES		10,994	
SOUTHBOUND					
242+00.00	289+22.60	INSIDE SHLD			3,148
236+60.00	241+84.00	OUTSIDE SHLD			582
248+00.00	289+22.60	EXISTING LANES		10,994	
CROSSOVERS					
270+42.00			149		
SUBTOTAL (FRANKLIN CO)=			149	21,987	7,485
WILLIAMSON CO.					
CROSSOVERS					
7+88			258		
135+77			486		
NORTHBOUND					
00+02.25	178+13.00	EXISTING LANES		48,673	
0+02.25	169+50.00	INSIDE SHLD			11,299
79+50.00	83+70.00	OUTSIDE SHLD			467
79+50.00	84+10.00	EXISTING LANES	1,227		
163+40.00	168+30.00	EXISTING LANES	1,307		
163+40.00	168+30.00	OUTSIDE SHLD			544
SOUTHBOUND					
00+02.25	177+73.00	EXISTING LANES		48,886	
0+02.25	167+90.00	INSIDE SHLD			11,192
79+20.00	84+40.00	OUTSIDE SHLD			578
79+20.00	84+40.00	EXISTING LANES	1,387		
163+15.00	168+30.00	EXISTING LANES	1,307		
163+15.00	165+55.00	OUTSIDE SHLD			267
SUBTOTAL (WILLIAMSON CO)=			5,970	97,559	24,346
TOTALS=			6,119	119,546	31,831

UNDERCUT LOCATION DETAILS

STATION	LOCATION	DEPTH	UNSUITABLE MATERIAL (CU YD)	ROCK FILL (TON)
WILLIAMSON CO.				
79+50 TO 83+70	NB 3 LANES (STIRITZ RD)	12" UNDERCUT	560	840
79+20 TO 84+40	SB 3 LANES (STIRITZ RD)	12" UNDERCUT	694	1040
163+40 TO 168+30	NB 3 LANES (HERRIN RD)	12" UNDERCUT	654	980
163+40 TO 166+50	SB 3 LANES (HERRIN RD)	12" UNDERCUT	414	620
166+50 TO 168+30	SB 2 EXISTING LANES	12" UNDERCUT	160	240

NOTE: Final locations determined by the engineer.

△ REVISED SHEET 10-22-2018

MODEL: Default
FILE NAME: P:\1108\B&E\BID\NTEC\Illinois.gov\PWD\DOT\Documents\DOT_Offices\District 9\Projects\78363\CADD\Drawings\CAD\Drawings\1019-031-0978363-18-schedule.dgn

USER NAME = rollavr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN -	REVISED -				57	**	=	191	20
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -								
PLOT DATE = 10/12/2018	DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO

** (X-4) R-2; (28-5-1, 28-5) R-1

*FRANKLIN / WILLIAMSON