

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
368	1919 VB-R-1	COOK	47	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
CONTRACT NO. 60C11				

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY I000-2A	BRIDGE X180-2A			
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	267	267				
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B, 4"	SQ YD	389	389				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.1	0.1				
40600300	AGGREGATE (PRIME COAT)	TON	0.5	0.5				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.1	0.1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	28	28				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	34		34			
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	51	51				
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	227	227				
42001300	PROTECTIVE COAT	SQ YD	374	374				
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	51	51				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2260	2260				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	551	551				
44000600	SIDEWALK REMOVAL	SQ FT	2260	2260				
44000700	APPROACH SLAB REMOVAL	SQ YD	178	178				
44003100	MEDIAN REMOVAL	SQ FT	785		785			
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	150	150				
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	160.1		160.1			
50300260	BRIDGE DECK GROOVING	SQ YD	903		903			
50300300	PROTECTIVE COAT	SQ YD	1420		1420			
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	7328		7328			
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	4310		4310			
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	490		490			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2310		2310			
50800515	BAR SPLICERS	EACH	328		328			

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY I000-2A	BRIDGE X180-2A			
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	297		297			
51500100	NAME PLATES	EACH	1		1			
52000020	PREFORMED JOINT SEAL 1 3/4"	FOOT	324		324			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	307		307			
<del>58100200</del>	<del>WATERPROOFING-MEMBRANE-SYSTEM</del>	<del>SQ YD</del>	<del>997</del>		<del>997</del>			
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	210		210			
58700300	CONCRETE SEALER	SQ FT	2460		2460			
59000200	EPOXY CRACK INJECTION	FOOT	109		109			
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	551	551				
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	112.5	112.5				
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1		1			
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1		1			
63200310	GUARDRAIL REMOVAL	FOOT	150	150				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	2	6			
67100100	MOBILIZATION	L SUM	1	0.5	0.5			
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	0.5	0.5			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	0.5	1.5			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	45	10	35			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	230	200	30			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2276	1553	723			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	6070	4069	2001			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2862	1942	920			
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	900		900			
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	900		900			
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1533	1533				
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	723		723			

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**FAP 368: PULASKI ROAD (NB)  
OVER BRC RAILROAD**  
SUMMARY OF QUANTITIES

Rev.