

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2831	(3140 & 3141) RS-2	COOK	32	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 100% STATE I000		Y025 KEDZIE 50% CITY 50% STATE PARKING		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	22		2		
40600300	AGGREGATE (PRIME COAT)	TON	115	106		9		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	21.0	19.5		1.5		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	720	720				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	381	332.5		48.5		
42001300	PROTECTIVE COAT	SQ YD	1724	1724				
44000109	BITUMINOUS REMOVAL OVER PATCHES 2 1/4"	SQ YD	2262	1972		290		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	4569	3984		585		
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	229	200		29		
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	277	242		35		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	917	800		117		
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	642	560		82		
55039700	STORM SEWERS TO BE CLEANED	FOOT	620	600		20		
60250200	CATCH BASINS TO BE ADJUSTED	EACH	31	27		4		
60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	12	10		2		
60254330	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	5	4		1		
60255500	MANHOLES TO BE ADJUSTED	EACH	41	35		6		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.9		0.1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.9		0.1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13576	13576				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	250	250				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7850	7850				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4060	4060				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 100% STATE I000		Y025 KEDZIE 50% CITY 50% STATE PARKING		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	205	205				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1760	1760				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	250	250				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7850	7850				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4060	4060				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	205	205				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	135	135				
* 84700600	DETECTOR LOOP REPLACEMENT	FOOT	2693	2693				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52				
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	13	13				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	5592	5162		430		
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	2392	2209		183		
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	57321	52931		4390		
X6020064	MANHOLES TO BE RECONSTRUCTED WITH NEW FRAME AND PERFORATED LID FOR CATCH BASINS AND MANHOLES, CHICAGO STANDARD	EACH	5	5				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	90	90				
78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	150	150				

8/21/2006 04:10:00 PM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev.