

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
203	11BR-1	WHITESIDE	43	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

Item No.	Item	Unit	80 % FED. 20% STATE			
			Total	X020-2A ROADWAY	X020-2A ROADWAY	X020-2A BRIDGE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6	—	6	—
20200100	EARTH EXCAVATION	CU YD	51	19	32	—
20300100	CHANNEL EXCAVATION	CU YD	26	—	26	—
20400800	FURNISHED EXCAVATION	CU YD	914	278	636	—
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	66	—	—	66
* 25000750	MOWING	ACRE	0.9	0.4	0.5	—
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	145	65	80	—
28000300	TEMPORARY DITCH CHECK	EACH	1	1	—	—
28000400	PERIMETER EROSION BARRIER	FOOT	1000	525	475	—
28000500	INLET AND PIPE PROTECTION	EACH	1	—	1	—
28100107	STONE RIPRAP, CLASS A4	SQ YD	438	—	—	438
28200200	FILTER FABRIC	SQ YD	438	—	—	438
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	528	298	230	—
35101400	AGGREGATE BASE COURSE, TYPE B	TON	86	22	64	—
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.5	—	2.5	—
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	222	111	111	—
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	627	280	347	—
44000700	APPROACH SLAB REMOVAL	SQ YD	114	57	57	—
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	900	461	439	—
44004300	PAVEMENT BREAKING	SQ YD	905	498	407	—
48101200	AGGREGATE SHOULDERS, TYPE B	TON	547	218	329	—
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	—	—	1
50200100	STRUCTURE EXCAVATION	CU YD	110	—	—	110
50300100	FLOOR DRAINS	EACH	12	—	—	12
50300225	CONCRETE STRUCTURES	CU YD	118.0	—	—	118.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	228.8	—	—	228.8
50300260	BRIDGE DECK GROOVING	SQ YD	336	—	—	336
50300300	PROTECTIVE COAT	SQ YD	673	111	111	451
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	47660	—	—	47660
51201300	FURNISHING STEEL PILES HP8X36	FOOT	551	—	—	551
51201600	FURNISHING STEEL PILES HP12X53	FOOT	537	—	—	537
51202700	DRIVING STEEL PILES	FOOT	1088	—	—	1088
51203300	TEST PILE STEEL HP8X36	EACH	1	—	—	1
51203600	TEST PILE STEEL HP12X53	EACH	1	—	—	1
51204600	METAL SHOES	EACH	22	—	—	22
51500100	NAME PLATES	EACH	1	—	—	1

* 25000750

PLOT DATE = 07/06
 PLOT SCALE = NONE
 USER NAME = CHANS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAS 203 (MOLINE ROAD)
 SECTION 11BR-1
 WHITESIDE COUNTY
 SCALE: VERT. DATE 12/05
 HORIZ. DRAWN BY ARR
 CHECKED BY JKC

(NON-PARTICIPATING) *SPECIALTY ITEM