

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
203	11BR-1	WHITESIDE	43	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID	PROJECT	

Item No.	Item	Unit	80 % FED. 20% STATE			
			Total	X020-2A	X020-2A	X020-2A
			QUANTITY	ROADWAY	ROADWAY	BRIDGE
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	144	—	144	—
54213450	END SECTIONS 15"	EACH	3	—	3	—
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	36	—	—	36
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	101	—	—	101
60801015	FLAP GATE 15"	EACH	1	—	1	—
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	412.5	175	237.5	—
* 63000130	STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)	FOOT	37.5	37.5	—	—
* 63100045	TRAFFIC BARRIER TERMINAL TYPE 2	EACH	1	1	—	—
* 63100085	TRAFFIC BARRIER TERMINAL TYPE 6	EACH	4	2	2	—
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	1	1	—
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	1	—	1	—
63200310	GUARDRAIL REMOVAL	FOOT	241	127	114	—
63500105	DELINEATORS	EACH	3	1	2	—
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	—	—
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	2	3	—
67100100	MOBILIZATION	L SUM	1	0.5	0.5	—
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3820	1910	1910	—
78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	3	5	—
78200520	BARRIER WALL MARKERS, TYPE B	EACH	4	2	2	—
78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	3	1	2	—
* A2007814	TREE, TILIA AMERICANA (AMERICAN LINDEN/BASSWOOD), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	6	6	—	—
X0325519	DRAIN FOR AGGREGATE BASE COURSE	SQ YD	14	6	8	—
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	246	75	171	—
X4066735	LEVELING BINDER (HAND METHOD), SUPERPAVE, N50	TON	3	1.5	1.5	—
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N50	TON	173	94	79	—
X4073071	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 9 1/2"	SQ YD	692	391	301	—
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	—	—	1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1	—	—	1
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	0.5	0.5	—
Z0002600	BAR SPLICERS	EACH	66	—	—	66
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5	—
Z0028415	GEO TECHNICAL REINFORCEMENT	SQ YD	772	436	336	—
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0.5	0.5	—

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAS 203 (MOLINE ROAD)
 SECTION 11BR-1
 WHITESIDE COUNTY

SCALE: VERT.
 HORIZ.
 DATE 12/05

DRAWN BY ARR
 CHECKED BY JKC