

SUMMARY OF QUANTITIES
CONSTRUCTION TYPE CODE: 0028

PAY CODE	DESCRIPTION	UNIT	QUANTITY
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	24
* 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	33
20200100	EARTH EXCAVATION	CU YD	145
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	15
25100630	EROSION CONTROL BLANKET	SQ YD	3,561
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	8
28000305	TEMPORARY DITCH CHECKS	FOOT	20
28000500	INLET AND PIPE PROTECTION	EACH	5
28000400	PERIMETER EROSION BARRIER	FOOT	1,247
28100107	STONE RIPRAP, CLASS A4	SQ YD	16
28200200	FILTER FABRIC	SQ YD	16
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	5
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	458
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	149
35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	260
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	590
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	59
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 TON	TON	45
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	45
40604162	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	30
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	52
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	458
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	8,486
42400800	DETECTABLE WARNINGS	SQ FT	140
44000100	PAVEMENT REMOVAL	SQ YD	263
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	621
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	482
52200800	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	366
54210190	PIPE ELBOW, 30"	EACH	2
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2
54260315	TRAVERSABLE PIPE GRATE FOR CONCRETE END SECTION	FOOT	24
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	38
56109210	WATER VALVES TO BE ADJUSTED	EACH	1
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	4
60262700	INLETS TO BE RECONSTRUCTED	EACH	1

* SPECIALTY ITEMS

CONTRACT NUMBER

85727

SUMMARY OF QUANTITIES
CONSTRUCTION TYPE CODE: 0028

PAY CODE	DESCRIPTION	UNIT	QUANTITY
60610100	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.18 (MODIFIED)	FOOT	482
67100100	MOBILIZATION	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	14
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	96
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	425
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	702
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	115
* 81028750	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA.	FOOT	29
* 81028760	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2-1/2" DIA.	FOOT	23
* 81028770	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 3" DIA.	FOOT	9
* 81028790	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 4" DIA.	FOOT	135
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	472
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	1
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	647
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,113
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,175
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	229
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	76
* 87301732	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 20 3C	FOOT	215
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	246
* 87500600	TRAFFIC SIGNAL POST, 10 FT.	EACH	1
* 87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	2
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	13
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	6
* 89501300	RELOCATE EXISTING MAST ARM ASSEMBLY AND POLE	EACH	1
* 89502376	REBUILD EXISTING HANDHOLE	EACH	1
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	1
X6026056	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
* X8760200	ACCESSIBLE PEDESTRIAN SIGNALS	EACH	6
XX000970	PARKWAY RESTORATION	L SUM	1
XX007759	ADJUST SANITARY SEWER CLEANOUT	EACH	12
Z0013798	CONSTRUCTION LAYOUT	L SUM	1

* SPECIALTY ITEMS

FEHR GRAHAM

ENGINEERING & ENVIRONMENTAL

ILLINOIS DESIGN FIRM NO. 184-003525

ILLINOIS
IOWA
WISCONSIN

OWNER/DEVELOPER:

CITY OF ROCKFORD
425 EAST STATE STREET
ROCKFORD, IL 61104

PROJECT AND LOCATION:

PARKVIEW AVENUE
ROCKFORD, ILLINOIS

DRAWN BY: BF
APPROVED BY: WK
DATE: 2/8/23
SCALE: AS NOTED

REVISIONS

REV. NO.	DESCRIPTION	DATE
1	BIDDING QUESTIONS	11/3/23

DRAWING:

SUMMARY OF QUANTITIES

SET TYPE:

c:\c30\2020-2024\Plan\20-304 Plans.dwg, Summary Only

JOB NUMBER:

20-394A

SHEET NUMBER:

5 of 49

