LETTING ITEM NO. 06A NOVEMBER 17, 2023 IDOT LETTING

IIEM	DESCRIPTION	UNII	QUANTITY	QUANTITY		
AR150520	MOBILIZATION	L SUM	1			
AR152410	UNCLASSIFIED EXCAVATION	CU YD	170			
AR152540	SOIL STABILIZATION FABRIC	SQ YD	50			
AR156520	INLET PROTECTION EACH		4			
AR201661	CLEAN AND SEAL BITUMINOUS CRACKS	FOOT	1,240			
AR201663	SAND MIX CRACK REPAIR	FOOT	940			
AR208515	POROUS GRANULAR EMBANKMENT	CU YD	20			
AR208604	4" AGGREGATE BASE COURSE	SQ YD	1,190			
AR208608	8" AGGREGATE BASE COURSE	SQ YD	50			
AR401610	BITUMINOUS SURFACE COURSE	TON	525			
AR401650	BITUMINOUS PAVEMENT MILLING	SQ YD	4,650			
AR401916	REM & REP BIT PAVEMENT - TYPE B	SQ YD	200			
AR602510	BITUMINOUS PRIME COAT	GALLON	60			
AR603510	BITUMINOUS TACK COAT	GALLON	685			
AR620520	PAVEMENT MARKING - WATERBORNE	SQ FT	140			
AR910200	ROADWAYSIGN EACH 1		1			
ITEM			ESTIMATED	RECORD		
ITEM	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY		
ITEM AS152410	DESCRIPTION UNCLASSIFIED EXCAVATION	UNIT CU YD	ESTIMATED QUANTITY 110	RECORD QUANTITY		
ITEM AS152410 AS152540	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC	UNIT CU YD SQ YD	ESTIMATED QUANTITY 110 150	RECORD QUANTITY		
ITEM AS152410 AS152540 AS156520	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC INLET PROTECTION	UNIT CU YD SQ YD EACH	ESTIMATED QUANTITY 110 150 2	RECORD QUANTITY		
ITEM AS152410 AS152540 AS156520 AS208515	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC INLET PROTECTION POROUS GRANULAR EMBANKMENT	UNIT CU YD SQ YD EACH CU YD	ESTIMATED QUANTITY 110 150 2 50	RECORD QUANTITY		
ITEM AS152410 AS152540 AS156520 AS208515 AS208604	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC INLET PROTECTION POROUS GRANULAR EMBANKMENT 4" AGGREGATE BASE COURSE	UNIT CU YD SQ YD EACH CU YD SQ YD	ESTIMATED QUANTITY 110 150 2 50 15	RECORD QUANTITY		
ITEM AS152410 AS152540 AS156520 AS208515 AS208604 AS208608	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC INLET PROTECTION POROUS GRANULAR EMBANKMENT 4" AGGREGATE BASE COURSE 8" AGGREGATE BASE COURSE	UNIT CU YD SQ YD EACH CU YD SQ YD SQ YD	ESTIMATED QUANTITY 110 150 2 50 15 150	RECORD QUANTITY		
ITEM AS152410 AS152540 AS156520 AS208515 AS208604 AS208608 AS401610	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC INLET PROTECTION POROUS GRANULAR EMBANKMENT 4" AGGREGATE BASE COURSE 8" AGGREGATE BASE COURSE BITUMINOUS SURFACE COURSE	UNIT CU YD SQ YD EACH CU YD SQ YD SQ YD TON	ESTIMATED QUANTITY 110 150 2 50 15 150 18	RECORD QUANTITY		
ITEM AS152410 AS152540 AS156520 AS208515 AS208604 AS208608 AS401610 AS401650	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC INLET PROTECTION POROUS GRANULAR EMBANKMENT 4" AGGREGATE BASE COURSE 8" AGGREGATE BASE COURSE BITUMINOUS SURFACE COURSE BITUMINOUS PAVEMENT MILLING	UNIT CU YD SQ YD EACH CU YD SQ YD SQ YD TON SQ YD	ESTIMATED QUANTITY 110 150 2 50 15 150 18 90	RECORD QUANTITY		
ITEM AS152410 AS152540 AS156520 AS208515 AS208604 AS208608 AS401610 AS401650 AS401916	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC INLET PROTECTION POROUS GRANULAR EMBANKMENT 4" AGGREGATE BASE COURSE 8" AGGREGATE BASE COURSE BITUMINOUS SURFACE COURSE BITUMINOUS SURFACE COURSE BITUMINOUS PAVEMENT MILLING REM & REP BIT PAVEMENT - TYPE B	UNIT CU YD SQ YD EACH CU YD SQ YD SQ YD TON SQ YD SQ YD SQ YD	ESTIMATED QUANTITY 110 150 2 50 15 150 15 150 18 90 100	RECORD QUANTITY		
ITEM AS152410 AS152540 AS156520 AS208515 AS208604 AS208608 AS401610 AS401650 AS401916 AS403610	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC INLET PROTECTION POROUS GRANULAR EMBANKMENT 4" AGGREGATE BASE COURSE 8" AGGREGATE BASE COURSE BITUMINOUS SURFACE COURSE BITUMINOUS SURFACE COURSE BITUMINOUS PAVEMENT MILLING REM & REP BIT PAVEMENT - TYPE B BITUMINOUS BASE COURSE	UNIT CU YD SQ YD EACH CU YD SQ YD SQ YD TON SQ YD SQ YD SQ YD TON	ESTIMATED QUANTITY 110 150 2 50 15 150 15 150 18 90 100 16	RECORD QUANTITY		
ITEM AS152410 AS152540 AS156520 AS208515 AS208604 AS208608 AS401610 AS401650 AS401916 AS403610 AS403610	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC INLET PROTECTION POROUS GRANULAR EMBANKMENT 4" AGGREGATE BASE COURSE 8" AGGREGATE BASE COURSE BITUMINOUS SURFACE COURSE BITUMINOUS PAVEMENT MILLING REM & REP BIT PAVEMENT - TYPE B BITUMINOUS BASE COURSE BITUMINOUS PRIME COAT	UNIT CU YD SQ YD EACH CU YD SQ YD SQ YD TON SQ YD SQ YD SQ YD TON GALLON	ESTIMATED QUANTITY 110 150 2 50 15 150 15 150 18 90 100 16 45	RECORD		
ITEM AS152410 AS152540 AS156520 AS208515 AS208604 AS208608 AS401610 AS401650 AS401916 AS403610 AS403510	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC INLET PROTECTION POROUS GRANULAR EMBANKMENT 4" AGGREGATE BASE COURSE 8" AGGREGATE BASE COURSE BITUMINOUS SURFACE COURSE BITUMINOUS PAVEMENT MILLING REM & REP BIT PAVEMENT - TYPE B BITUMINOUS PARE COURSE BITUMINOUS BASE COURSE BITUMINOUS PRIME COAT BITUMINOUS TACK COAT	UNIT CU YD SQ YD EACH CU YD SQ YD SQ YD TON SQ YD SQ YD TON GALLON GALLON	ESTIMATED QUANTITY 110 150 2 50 15 150 15 150 18 90 100 16 45 25	RECORD QUANTITY		
ITEM AS152410 AS152540 AS156520 AS208515 AS208608 AS208608 AS401610 AS401650 AS401610 AS403610 AS403610 AS403610 AS603510 AS701515	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC INLET PROTECTION POROUS GRANULAR EMBANKMENT 4" AGGREGATE BASE COURSE 8" AGGREGATE BASE COURSE BITUMINOUS SURFACE COURSE BITUMINOUS PAVEMENT MILLING REM & REP BIT PAVEMENT - TYPE B BITUMINOUS PARE COURSE BITUMINOUS PAVEMENT MILLING REM & REP BIT PAVEMENT - TYPE B BITUMINOUS PRIME COAT BITUMINOUS PRIME COAT BITUMINOUS TACK COAT 15" RCP, CLASS IV	UNIT CU YD SQ YD EACH CU YD SQ YD SQ YD TON SQ YD SQ YD TON GALLON GALLON FOOT	ESTIMATED QUANTITY 110 150 2 50 15 150 15 150 18 90 100 16 45 25 16	RECORD		
ITEM AS152410 AS152540 AS156520 AS208515 AS208604 AS208608 AS401610 AS401650 AS401650 AS401916 AS403610 AS602510 AS603510 AS701515 AS752415	DESCRIPTION UNCLASSIFIED EXCAVATION SOIL STABILIZATION FABRIC INLET PROTECTION POROUS GRANULAR EMBANKMENT 4" AGGREGATE BASE COURSE 8" AGGREGATE BASE COURSE BITUMINOUS SURFACE COURSE BITUMINOUS PAVEMENT MILLING REM & REP BIT PAVEMENT - TYPE B BITUMINOUS PRIME COAT BITUMINOUS TACK COAT 15" RCP, CLASS IV PRECAST REINFORCED CONC. FES 15"	UNIT CU YD SQ YD EACH CU YD SQ YD SQ YD TON SQ YD SQ YD TON GALLON GALLON FOOT EACH	ESTIMATED QUANTITY 110 150 2 50 15 150 15 150 18 90 100 16 45 25 16 16 1	RECORD		

JOINT UTILITY LOCATING

www.illinois1call.com

COUNTY: KANE

U.S. ROUTE 30

SUGAR GROVE TOWNSHIP

THE LOCATION SIZE AND TYPE OF MATERIAL OF EXISTING LINDERGROUND

UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO

DETERMINE ACTUAL LOCATIONS OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES OF HIS OPERATIONAL PLANS,

OBTAIN FROM RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND

ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED

IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING

CONSTRUCTION THE CONTRACTOR SHALL IMMEDIATELY NOTICY THE LITH ITY

COMPANY OF JURISDICTION AND THE ONE-CALL NOTICE SYSTEM. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH UTILITY OR SERVICES SHALL BE

RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

CALL J.U.L.I.E BEFORE EXCAVATING

AT 811

AURORA MUNICIPAL AIRPORT

INFORMATION FOR EXCAVATORS

Know what's below

SECTION: 17 AND 18

TOWNSHIP: 38 NORTH

RANGE: 7 EAST

Call before you dig.

CITY OF AURORA AURORA, ILLINOIS

FOR AURORA MUNICIPAL AIRPORT

OVERLAY SOUTHEAST QUADRANT AIRPORT PERIMETER ROADWAYS - PHASE 2

ILLINOIS PROJECT: ARR-4565



SEPTEMBER 22, 2023

D Ryle Realvery

LICENSE EXPIRATION DATE: 11/30/2023 DATE SIGNED: 09/29/2023





LOCATION MAP

ON MAP

AU073 TOTAL SHEETS: 8



NOTES

- AT ALL TIMES THE CONTRACTOR SHALL PERFORM ALL MAINTENANCE WORK NECESSARY TO KEEP EACH NEWLY CONSTRUCTED PAVEMENT SECTION LAYER IN A SATISFACTORY CONDITION.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DAMAGE DONE BY HIS HAULING AND CONSTRUCTION EQUIPMENT. ANY WORK NECESSARY TO CORRECT DAMAGED WORK AND EXISTING PAVEMENT SHALL BE PERFORMED BY THE CONTRACTOR AND AT THE EXPENSE OF THE CONTRACTOR.
- 3. THE CONTRACTOR SHALL TAKE THE NECESSARY PRECAUTIONS TO PROTECT THE PAVEMENT STRUCTURE AND SUBGRADE FROM DAMAGE, WHICH MAY INCLUDE BUT NOT BE LIMITED TO USE OF TRACKED EQUIPMENT, SHORT HAUL TRUCKS OR TRACKED PAVERS, AT NO ADDITIONAL COST TO THE CONTRACT.
- 4. THE CONTRACTOR WILL BE REQUIRED TO FURNISH AND PLACE CONSTRUCTION LAYOUT STAKES FOR THIS PROJECT. CONSTRUCTION LAYOUT SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE PAY ITEM FOR WHICH THE LAYOUT IS REQUIRED.
- 5. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND/OR TEMPORARY EASEMENTS FOR THE PUBLIC ACCESS ROAD(S) SHOWN AND SHALL COMPLY WITH ALL REQUIREMENTS, LOAD RESTRICTIONS AND TRAFFIC CONTROL SIGNAGE REQUIRED BY THE CITY, COUNTY, TOWNSHIP OR I.D.O.T. COST INCIDENTAL TO THE CONTRACT
- 6. CONTRACTOR SHALL BE REQUIRED TO OBTAIN AN IDOT HIGHWAY PERMIT FOR WORK WITHIN THE RIGHT-OF-WAY OF U.S. ROUTE 30. ALL FEES AND CHARGES INCURED BY THE CONTRACTOR TO OBTAIN THE NECESSARY PERMITS/PERMISSIONS TO INSTALL AND PERFORM THE WORK SHALL BE NOT MEASURED SEPARATELY FOR PAYMENT BUT SHALL BE INCIDENTAL TO CONTRACT (ADDITIVE ALTERNATE NO. 1 WORK)
- SCOPE OF WORK FOR ADDITIVE ALTERNATE NO. 1 INCLUDES INTERSECTION WIDENING AND REMOVE AND REPLACE BITUMINOUS PAVEMENT TYPE B WITHIN THE U.S. 30 RIGHT OF WAY. THIS INCLUDES ALL 7. PLACEMENT, REMOVAL AND FOR ALL LABOR, EQUIPMENT, TOOLS AND INCIDENTALS NECESSARY TO COMPLETE THIS SCOPE OF WORK.

U.S. ROUTE 30

THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ARCHITECT/ENGINEER ASSUMES ANY

RESPONSIBILITY WHATSOEVER WITH RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES,

INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL, BELOCATION OR ADJUSTMENT WHERE BEQUIRED IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE

UTILITY COMPANY OF JURISDICTION. THE ARCHITECTENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOF BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

VERTICAL CONTROL			
POINT	DESCRIPTION	ELEVATION	
BM-1	N.W. CORNER FLAG POLE FOUNDATION	703.61	
VERTICAL CONTROL COORDINATES EXPRESSED IN NAD88			

HORIZONTAL CONTROL				
POINT	DESCRIPTION	NORTHING	EASTING	
CP-200	IRON ROD	1857161.440	950033.670	
CP-201	IRON ROD	1857182.655	949499.807	
HORIZONTAL CONTROL COORDINATES EXPRESSED IN NAD83				

ALIGNMENT DATA

NORTHING/

EASTING

POINT

STATION NORTHING

FASTING

STATION

F

ALIGNMENT

POINT

1 BASELINE A 0+00.00 1857205.164 2 22+63.32 1857221.875 948894.960 950111.867 BASELINE B 1858168.801 1857071.598 3 0+00.00 4 10+97.28 950064.693 950070.849 AIRFIELD EXISTING UGS ADMINISTRATION FUEL FARM BUII DING ATCT *!*"} **BEHABII ITATE** ENGINEER'S AUTO PARKING FIELD OFFICE LOTS AND ENTRANCE ROAD (BY OTHERS) вма REHABILITATE AUTO PARKING LOTS AND PARKW ENTRANCE ROAD (BY OTHERS) **10RIAL** SOUTH APRON Ĩ **/ETERANS** REHABILITATE AUTO PARKING LOTS AND ENTRANCE ROAD (BY OTHERS) 17+00 <u>18+00</u> 20+00 16+00 15+00 12+00 13+00 14+00 10+00 6+00 7+00 8+00 9+00 4+00 5+00 1+00 2+00 3+00CP-201/0 AIRPORT PERIMETER ROAD BASELINE A



STORM WATER POLLUTION PREVENTION NOTES

THE FOLLOWING IS TO ESTABLISHED BEST MANAGEMENT PRACTICES TO BE INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME.

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEFRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING, WHICH WILL BE THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

SITE DESCRIPTION

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN

THIS PROJECT CONSISTS OF CONSTRUCTING AN OVERLAY, PAVEMENT PATCHING AND PAVEMENT MILLING AT AURORA MUNICIPAL AIRPORT.

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS EXCAVATION AND GRADING:

1. UNCLASSIFIED EXCAVATION (PGE AND AGGREGATE BASE COURSE SHALL BE CONSTRUCTED THE SAME DAY AS THE EXCAVATION)

2. 4" AGGREGATE BASE FOR SHOULDERS.

AREA OF CONSTRUCTION SITE

THE TOTAL AREA OF THE CONSTRUCTION SITE THAT WILL BE DISTURBED BY EXCAVATION AND OTHER ACTIVITIES IS LESS THAN ONE (1) ACRE.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE

THE CONSTRUCTION SITE DRAINS INTO STORM SEWERS THAT OUTLET INTO THE WELCH CREEK

SEDIMENTATION AND EROSION CONTROL NOTES

THE RESIDENT ENGINEER WILL PERFORM PERIODIC INSPECTION OF THE SITE TO IDENTIFY POTENTIAL SEDIMENT AND EROSION ISSUES.

ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES ARE REFERENCED FROM THE ILLINOIS URBAN MANUAL, UNLESS OTHERWISE STATED.

THE DRAWINGS, SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE SEEDING AND MULCHING AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED WITHIN SEVEN (7) DAYS OF DISTURBANCE

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES

- 1. WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION.
- 2. EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTORS EXPENSE, IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.
- 3. AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER
 - A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS.
- B. EXCAVATED AREAS AND EMBANKMENT AREAS SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT, THEY SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTOR'S COST. IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR SEVEN DAYS
- 4. CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS, ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.
- 5. SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF OFF SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCIDENTAL TO THE COST OF THE PROJECT
- 6. THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCIDENTAL TO THE CONTRACT.

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED.

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED.

MAINTENANCE AFTER CONSTRUCTION

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR.



- FILTER WRAP TO BE PLACED IN ALL SLOPE BOX INLETS, INLETS, MANHOLES, TRENCH DRAINS AND CATCH BASINS LOCATED IN PAVED AREAS AND NONPAVED AREAS
- FABRIC SHALL BE IN CONFORMANCE WITH ARTICLE 1080.03 OF THE IDOT STANDARD 2. SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION 2022
- З. FABRIC SHALL OVERLAY FRAME BY 2" (MIN.).

MAXIMUM ENCH WID

3'-7"

3'-9"

4'-6"

4'-9"

5'-0"

5'-4"

5'-7"

5'-11"

6'-6"

7'-1"

7'-8"

8'-3"

8'-10"

9'-5"

10'-0"

11'-2"

11'-9"

12'-4"

12'-11'

13'-6"

6

8

12 4'-2"

15

18

21

24

27

30

36

42

48

54

60

66

72

78 84

90

96

102

108

- CONTRACTOR SHALL CLEAR DEBRIS AND SILT AS REQUIRED FROM FABRIC TO MAINTAIN 4. DRAINAGE THROUGH THE STRUCTURE.
- FABRIC SHALL REMAIN IN PLACE UNTIL COMPLETION OF PAVEMENT REHABILITATION 5.
- COST OF FILTER WRAP AND MAINTENANCE SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. 6

AU073

INSTALLATION OF PROPOSED PIPE

CONSULTANTS

FINAL

OVERLAY SOUTHEAST QUADRANT AIRPORT PERIMETER ROADWAYS - PHASE 2

SEPTEMBER 22. 2023





MARK DATE DESCRIPTION

IL PROJECT NO:	ARR-4565
CMT PROJECT NO:	21002029.00
CAD DWG FILE:	
DESIGNED BY:	STL
DRAWN BY:	JRO
CHECKED BY:	STL
APPROVED BY:	DLP
COPYRIGHT	

SHEET TITLE

STORM WATER POLLUTION PREVENTION NOTES AND DETAILS

SHEET

3

OF

8



GENERAL NOTES

- THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE PROPOSED IMPROVEMENTS WHILE MAINTAINING VEHICLE ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION. OF THE AIRPORT MANAGER AND RESIDENT ENGINEER AND BE APPROVED BY IDOT AERONAUTICS AND FEDERAL AVIATION ADMINISTRATION.
- 2 ALL OPERATIONS SHALL BE IN CONFORMANCE WITH AC 150/5370-2 (LATEST EDITION) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION"
- CONTRACTOR'S EQUIPMENT SHALL BE STORED IN THE EQUIPMENT AND MATERIAL STORAGE/STAGING AREA WHEN CONSTRUCTION IS NOT IN PROGRESS. NO EXCEPTIONS FOR SLOW MOVING EQUIPMENT SHALL BE ALLOWED.
- THE AIRPORT MANAGER SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATING PHASING AND SEQUENCE AS IT RELATES TO PEDESTRIAN AND VEHICULAR SAFETY.
- 5. ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED AS A HAUL ROAD OR STORAGE AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER. THE COST OF MAINTAINING, REPAIRING OR CONSTRUCTING THESE PAVEMENTS AND AREAS SHALL BE INCIDENTAL TO THE CONTRACT. EXISTING AREAS OUTSIDE THE PROJECT LIMITS WHICH ARE DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE AIRPORT MANAGER.
- THE CONTRACTOR SHALL KEEP ALL TRUCKS. EQUIPMENT AND MATERIALS OFF OF THE TENANT PARKING LOTS AND DRIVEWAYS OUTSIDE OF THE 6 PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE ENGINEER AND AIRPORT
- WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT SHALL CONSIST OF MOVABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE. LIGHTING SHALL BE AS APPROVED BY THE ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY. CONTRACTOR'S WORK HOURS SHALL BE IN ACCORDANCE WITH LOCAL ORDINANCES.
- THE CONTRACTOR WILL BE REQUIRED TO HAVE A SWEEPER AVAILABLE FOR USE AT ALL TIMES. MATERIAL TRACKED ON TO THE PAVEMENT SHALL BE CONTINUALLY REMOVED WITH SAID SWEEPER. THIS SWEEPING SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- MATERIALS REMOVED FROM THE PROJECT WILL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS NOTED OTHERWISE.
- 10. PAYMENT FOR TRAFFIC CONTROL INCLUDING, BUT NOT LIMITED TO BARRICADES, CONSTRUCTION FENCE, SIGNING, ETC. SHALL NOT BE PAID SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. BARRICADES SHALL HAVE FLASHING LIGHT(S) AND CONFORM TO IDOT STANDARD 701901-07 AND TYPE III SIGNS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- 11. THE CONTRACTOR SHALL CONTACT THE AIRPORT MANAGER THROUGH THE RESIDENT ENGINEER TEN (10) WORKING DAYS IN ADVANCE OF THE START OF CONSTRUCTION SO THAT THE APPROPRIATE NOTAMS MAY BE ISSUED.
- 12. IN THE CASE OF AN EMERGENCY, CONTRACTOR SHALL NOTIFY AIRPORT MANAGER AND THE RESIDENT ENGINEER IMMEDIATELY,
- 13. DURING ADVERSE WEATHER, THE CONTRACTOR SHALL MAKE PROVISIONS FOR ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT. NO EXTENSION OF CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK.
- 14. AURORA MUNICIPAL AIRPORT WILL BE IN OPERATION DURING THE CONSTRUCTION OF THIS PROJECT. COORDINATION OF WORK WITH THE AIRPORT IS MANDATORY SO AS TO MINIMIZE IMPACTS ON AIRPORT OPERATIONS
- 15. APPROXIMATE LOCATION OF HAUL ROUTES ON THE AIRPORT SITE ARE SHOWN ON THE GENERAL PROJECT LAYOUT AND THE PHASING PLANS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE HAUL ROUTES (STATE HIGHWAYS, COUNTY ROADS OR CITY STREETS) WITH THE APROPRIATE OWNER WHO HAS JURISDICTION OVER THE AFFECTED ROUTE. ON-SITE ROADS USED AS HAUL ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR AND SHALL BE RESTORED AT THE CONTRACTOR'S EXPENSE TO THEIR ORIGINAL CONDITION UPON COMPLETION OF BEING USED AS A HAUL ROUTE. THE BEFORE AND AFTER CONDITION OF ON-SITE HAUL ROUTES SHALL BE JOINTLY INSPECTED AND DETERMINED BY THE CONTRACTOR AND THE ENGINEER. FENCING, DRAINAGE, GRADING AND OTHER MISCELLANEOUS CONSTRUCTION REQUIRED TO CONSTRUCT TEMPORARY HAUL ROUTES OR ACCESS POINTS ON THE AIRPORT WILL BE THE CONTRACTOR'S TOTAL RESPONSIBILITY AND SHALL BE APPROVED BY THE ENGINEER PRIOR TO THE WORK. ALL ON-SITE ACCESS ROADS TO AIRPORT FACILITIES SHALL REMAIN OPEN AND MAINTAINED AT ALL TIMES.
- 16. MOBILIZATION/EQUIPMENT STORAGE AREA WILL BE MADE AVAILABLE FOR CONTRACTOR'S MOBILIZATION AND STORAGE AS SHOWN ON THE PLANS. THIS AREA SHALL BE RESTORED TO THE ORIGINAL CONDITION UPON COMPLETION OF THE PROJECT AT THE CONTRACTOR'S EXPENSE.
- 17. LOCATION OF KNOWN EXISTING AIRPORT UNDERGROUND CABLES ARE SHOWN ON THE PLANS AND MUST BE VERIFIED BY THE CONTRACTOR. REPAIR OF DAMAGED CABLE MUST BE STARTED IMMEDIATELY AND CONTINUED UNTIL COMPLETED. ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS, OR AS DIRECTED BY THE OWNER OF THE CABLE OR FACILITY, AND SHALL BE AT THE CONTRACTOR'S EXPENSE. IF FAA CABLES ARE DAMAGED, REPAIRS SHALL BE DONE FROM PREVIOUS EXISTING TERMINATION POINT TO PREVIOUS EXISTING TERMINATION POINT IN ACCORDANCE WITH FAA REQUIREMENTS AND IN THE PRESENCE OF A FAA REPRESENTATIVE. THE OWNER MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHERS IN WHICH CASE THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING THE INCURRED COSTS OF REPAIRS
- COORDINATION MEETINGS THE CONTRACTOR SHALL CONDUCT WEEKLY COORDINATION MEETINGS TO DISCUSS WORK AREAS AND SCHEDULING, ETC. WITH THE ENGINEER, AIRPORT OPERATIONS, FAA, AND OTHER APPROPRIATE OFFICIALS. MINUTES FROM THE WEEKLY MEETINGS SHALL BE PREPARED BY THE CONTRACTOR, FURNISHED TO ALL ATTENDEES PRIOR TO THE SUBSEQUENT MEETING, AND KEPT ON FILE AT THE FIELD OFFICE. THE COORDINATION MEETING COSTS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
- 19. THE CONTRACTOR SHALL PROVIDE THE PHONE NUMBERS OF THREE PERSONNEL, INCLUDING THE PROJECT SUPERINTENDENT, WHO MAY BE CONTACTED IN AN EMERGENCY. PERSONNEL SHALL BE ON CALL 24 HOURS PER DAY FOR MAINTAINING AIRPORT HAZARD LIGHTING AND BARRICADES
- 20. COORDINATION BY THE CONTRACTOR WITH THE EXISTING UTILITIES SHALL BE COMPLETED BEFORE CONSTRUCTION IS STARTED. CONTRACTOR IS REFERRED TO SECTION 50-17 OF THE SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER OR THE DESIGN ENGINEER ASSUME ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED THAT THE LOCATIONS, SIZE AND TYPE MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES, PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE RESIDENT ENGINEER AND THE AIRPORT MANAGER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER.

- CCONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS OR A WORKING BEACON LIGHT ON ALL EQUIPMENT AT ALL TIMES DURING 21 CONSTRUCTION, SEE FLAG DETAIL
- PREPARE A SAFETY PLAN COMPLIANCE DOCUMENT. THE SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) DETAILS HOW THE CONTRACTOR 22. WILL COMPLY WITH THE CSPP. ALSO, IT WILL NOT BE POSSIBLE TO DETERMINE ALL SAFETY PLAN DETAILS (FOR EXAMPLE SPECIFIC HAZABD EQUIPMENT AND LIGHTING. CONTRACTOR'S POINTS OF CONTACT, CONSTRUCTION FOURPMENT HEIGHTS) DURING THE DEVELOPMENT OF THE CSPP. THE SUCCESSFUL CONTRACTOR MUST DEFINE SUCH DETAILS BY PREPARING AND SPCD THAT IN CONFORMANCE WITH FAA AC 150/5370-2 (LATEST EDITION) PRIOR TO ISSUANCE OF A NOTICE-TO-PROCEED. THE SPCD IS A SUBSET OF THE CSPP, SIMILAR TO HOW A SHOP DRAWING REVIEW IS A SUBSET TO THE TECHNICAL SPECIFICATIONS

CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS, WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS. THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS SUBCONTRACTORS. IT IS ANTICIPATED THE FOLLOWING PROJECTS MAY BE UNDER CONSTRUCTION CONCURRENTLY WITH THIS PROJECT NO ADDITIONAL COMPENSATION SHALL BE CONSIDERED FOR ANY EFFORTS TO COORDINATE AND ACCESS THE SITE DUE TO ADJACENT CONSTRUCTION.

REHABILITATE AUTO PARKING LOTS AND ENTRANCE ROAD (IL. PROJECT NO. 4544)

REVV AVIATION FUEL FARM PROJECT.

TABLE 1 - CRITICAL POINTS					
POINT	APPROXIMATE ELEVATION OF GROUND (NAV 83)	ANTICIPATED EQUIPMENT AND HEIGHT	APPROXIMATE ELEVATION OF EQUIPMENT (NAV 83)	LATITUDE (NAD 83)	LONGITUDE (NAD 83)
CP1	703.6	SEMI/DUMP TRUCK - 25'	728.6	41° 45' 56.34"	88° 27' 46.23"
CP2	702.5	SEMI/DUMP TRUCK - 25'	727.5	41° 46' 05.38"	88° 27' 31.13"
CP3	702.5	SEMI/DUMP TRUCK - 25'	727.5	41° 46' 05.29"	88° 27' 31.13"
CP4	703.2	SEMI/DUMP TRUCK - 25'	728.2	41° 46' 02.71"	88° 27' 31.10"



CONSTRUCTION EQUIPMENT AND TRUCK SIGNAL FLAG NOT TO SCALE





LOCATION DETAIL

NOT TO SCALE



CONSULTANTS

FINAL

OVERLAY SOUTHEAST QUADRANT AIRPORT PERIMETER ROADWAYS - PHASE 2

SEPTEMBER 22. 2023



OWNEE



MARK DATE DESCRIPTION

IL PROJECT NO ARR-4565 CMT PROJECT NO 21002029.00 CAD DWG FILE: DESIGNED BY STI DRAWN BY JRO CHECKED BY STL APPROVED BY DLP COPYRIGHT

SHEET TITLE

SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS

SHEET

5

OF

8







ath: K:\AuroraAp\21002029-00_OverlaySEQuadRdPh2\Draw\Sheets\2100202900 - swppp and marking tio: Monday Orchows 0, 2023 12-55-06 PM