FREEPORT - ALBERTUS AIRPORT

Know what's below.

DATE

COMMON GROUND ALLIANCE www.call811.com or Phone: 811

THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

9/22/2023

TOWNSHIP: 26 NORTH RANGE: 8 EAST SECTION: 21 COUNTY: STEPHENSON TOWNSHIP: SILVER CREEK



CMT DESIGN NUMBER: 21001617.00

CITY OF FREEPORT FREEPORT, ILLINOIS


CONSTRUCTION PLANS FOR FREEPORT - ALBERTUS AIRPORT


CONSTRUCT SOUTHWEST TERMINAL AREA ENTRANCE ROAD, PHASE 2

FINAL DESIGN SUBMITTAL

ILLINOIS PROJECT: FEP-4489

SEPTEMBER 22, 2023 (NOVEMBER 17, 2023 LETTING)





SITE PLAN

FR047 TOTAL SHEETS: 25

DESIGN INFORMATION

GEOMETRIC CRITERIA

LOW SPEED URBAN STREET 20 MPH DESIGN SPEED

PAVEMENT DESIGN CRITERIA

AVERAGE DAILY TRAFFIC (ADT) < 400

MAXIMUM EQUIPMENT HEIGHT - 25'
UNICOM FREQUENCY - 122.80

INDEX TO SHEETS


- 1. COVER SHEET / INDEX TO SHEETS
- 2. SUMMARY OF QUANTITIES
- 3. SITE PLAN AND CONTROL 1
- 4. SITE PLAN AND CONTROL 2
- 5. SEQUENCE OF CONSTRUCTION
- 6. SEQUENCE OF CONSTRUCTION NOTES AND DETAILS
- 7. EXISTING CONDITIONS AND REMOVALS 1
- 8. EXISTING CONDITIONS AND REMOVALS 2
- 9. TYPICAL SECTIONS
- 10. PLAN AND PROFILE 1
- 11. PLAN AND PROFILE 2
- 12. PLAN AND PROFILE 3
- 13. PLAN AND PROFILE 4
- 14. GRADING PLAN 1
- 15. GRADING PLAN 2
- 16. GRADING PLAN 3
- 17. GRADING PLAN 4
- 18. ELECTRICAL PLAN 1
- 19. ELECTRICAL PLAN 220. ELECTRICAL PLAN 3
- 21. ELECTRICAL DETAILS
- 22. SWPPP / LANDSCAPING / MARKING PLAN 1
- 23. SWPPP / LANDSCAPING / MARKING PLAN 2
- 24. SWPPP NOTES
- 25. SWPPP DETAILS

| | SUMMARY OF QUANTI | TIES | | | | |
|--------------|--|--------|--------------------|--------------------|---|------------------------------------|
| ITEM NO. | DESCRIPTION | UNIT | ESTIMATED QUANTITY | RECORD QUANTITY | G | |
| AR109210 VA | ULT MODIFICATIONS | L SUM | 1.00 | | | Engineers and Consulta |
| AR110013 3" | DIRECTIONAL BORE | FOOT | 150.00 | | | |
| AR150510 EN | IGINEER'S FIELD OFFICE | L SUM | 1.00 | | | |
| AR150520 MC | DBILIZATION | LSUM | 1.00 | | F | FR047 |
| AR152410 UN | ICLASSIFIED EXCAVATION | CU YD | 270.00 | | | |
| AR152540 SC | DIL STABILIZATION FABRIC | SQYD | 425.00 | | | |
| AR156520 INL | LET PROTECTION | EACH | 12.00 | | | FREEPORT - ALBER |
| AR208515 PC | PROUS GRANULAR EMBANKMENT | CU YD | 140.00 | | | AIRPORT |
| AR209608 CF | RUSHED AGG. BASE COURSE - 8" | SQYD | 425.00 | | E | FREEPORT, IL |
| AR209704 CF | RUSHED AGG. SHOULDER - 4" | SQYD | 2,100.00 | | | |
| AR401610 BIT | TUMINOUS SURFACE COURSE | TON | 1,450.00 | | | CITY OF FREEPO |
| AR401650 BIT | TUMINOUS PAVEMENT MILLING | SQYD | 260.00 | | | ILLINOIS |
| AR401910 RE | MOVE & REPLACE BIT. PAVEMENT | SQYD | 80.00 | | | |
| AR403610 BIT | TUMINOUS BASE COURSE | TON | 40.00 | | D | IL Proj: |
| AR602510 BIT | TUMINOUS PRIME COAT | GALLON | 130.00 | | | FEP-4489 |
| AR603510 BIT | TUMINOUS TACK COAT | GALLON | 1,300.00 | | | APPROVED AS WORKING PLAN |
| AR620520 PA | VEMENT MARKING-WATERBORNE | SQFT | 650.00 | | | BY: |
| AR800802 2# | 8 XLP-USE, 1 #8 GND IN UD | FOOT | 1,500.00 | | | |
| AR800803 LIG | GHTING CONTROLLER/ELECTRIC SERVICE | LSUM | 1.00 | | С | |
| AR800804 RE | MOVE & REPLACE FULL DEPTH PAVEMENT STRUCTURE | SQYD | 25.00 | | | |
| AR901510 SE | EDING | ACRE | 1.10 | | | REV DATE DESCRIPTION PROJECT NAME: |
| AR908510 ML | JLCHING | ACRE | 1.10 | | | CONSTRUCT SOUTH |
| AR910100 RC | DADWAY LIGHT POLE | EACH | 8.00 | | | TERMINAL AREA ENTE |
| AR910900 RE | MOVE ROADWAY LIGHT POLE | EACH | 2.00 | | В | ROAD, PHASE 2 |
| AR910975 RE | ELOCATE ROADWAY SIGN | EACH | 2.00 | | | SHEET TITLE: SUMMARY OF |

2

ERTUS

PORT



THWEST ITRANCE

| BEGIOITEB. | Di G ttvi ti | 0.120.0 |
|--------------|--------------|---------|
| CMT-MLI | CMT-MLI | CMT-N |
| PROJECT NO : | 21001617 | . 00 |


REVISION


6


D

C


В











3 **GENERAL** 5. CONTRACTOR ACCESS TO THE FAA FOR AN AIRSPACE STUDY. NO EQUIPMENT WITH A HEIGHT CONSTRUCTION SAFETY AND PHASING PLAN SHEET OR AS DIRECTED BY GREATER THAN 25' SHALL BE USED UNTIL A DETERMINATION FROM FAA IS THE RESIDENT ENGINEER. THE CONTRACTOR SHALL PLACE ALL THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL FOLLOW THE CONTRACTOR ACCESS SHALL BE AS NOTED BELOW AND AS SHOWN ON BARRICADES AND CONSTRUCTION SETBACK LINES ITEMS AS SHOWN REQUIREMENTS OF THE AIRPORT'S APPROVED CONSTRUCTION SAFETY THE SITE PLAN AND CONSTRUCTION SAFETY AND PHASING PLAN SHEETS. PRIOR TO INITIATING WORK IN EACH PHASE. ALL COSTS TO FURNISH, AND PHASING PLAN (CSPP), FAA AC 150/5370-2(LATEST EDITION), AND ALL IN THE EVENT OF AN EMERGENCY, THE CONTRACTOR SHALL CALL 911. INSTALL, REPOSITION, AND MAINTAIN THESE ITEMS SHALL BE CONSIDERED Н AIRPORT SAFETY AND SECURITY REQUIREMENTS THE CONTRACTOR IS TO ACCESS THE SITE USING THE EXISTING GATE INCIDENTAL TO THE PROJECT. SHOWN. THE ENTRANCE SHALL BE SIGNED ACCORDINGLY AS TO ALLOW CONTACTS FOR THIS PROJECT WILL BE DETERMINED AT THE PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL ONLY CONSTRUCTION VEHICLES ACCESS AND WILL ONLY BE ACCESSIBLE PRECONSTRUCTION MEETING PRIOR TO THE PROJECT START. THE CONTRACTOR SHALL INSPECT THE BARRICADES ONCE DURING EACH SUBMIT TO THE AIRPORT FOR APPROVAL A SAFETY PLAN COMPLIANCE DURING THE CONTRACTOR'S SCHEDULED WORK DAY. ALL SIGNAGE SHALL WORK DAY TO INSURE PROPER PLACEMENT AND PROPER OPERATION OF DOCUMENT (SPCD) IN ACCORDANCE WITH FAA AC 150/5370-2(LATEST CONFORM TO CITY OF MOLINE AND IDOT CONSTRUCTION STANDARDS FOR 10. INSPECTION REQUIREMENTS THE RED LIGHTS AND FLAG PLACEMENT. EDITION). NO CONSTRUCTION ACTIVITY SHALL BEGIN UNTIL THE AIRPORT VEHICLES ENTERING AND LEAVING THE SITE. FREEPORT - ALBERTUS THE CONTRACTOR SHALL INSPECT THE JOBSITE DAILY TO ENSURE HAS APPROVED THE SPCD. **AIRPORT** ACCESS TO ACTIVE RUNWAY AND TAXIWAY PAVEMENTS (TOWER SUPERVISORY PERSONNEL SHALL DEMONSTRATE IN THE PRESENCE OF COMPLIANCE WITH THE CSPP. THE CHECKLIST FOUND IN APPENDIX 3 OF CONTROLLED AREAS) SHALL BE SIGNED WITH STOP SIGNS MOUNTED ON THE CSPP COVERS OPERATIONAL SAFETY. THE CONTRACTOR SHALL BE THE AIRPORT MANAGER THAT THEY ARE FAMILIAR WITH AIRPORT RADIO FAA AC 150/5370-2F MAY BE USED TO AID IN THE INSPECTIONS. TYPE II BARRICADES (2 EACH, RIGHT AND LEFT). IN ADDITION TO THE STOP RESPONSIBLE FOR THE INDIVIDUAL SAFETY OF HIS/HER PERSONNEL AND AND AIRPORT DRIVING PROCEDURES IN ORDER TO PERFORM WORK SIGNS, WARNING SIGNS (2 EACH, RIGHT AND LEFT) SHALL BE MOUNTED. MEETING SAFETY REQUIREMENTS. OTHER CONSTRUCTION PERSONNEL CAN BE WITHIN THE AIRFIELD LIMITS THE CONTRACTOR SHALL ATTEND AN INSPECTION OF EACH PHASE WORK WARNING SIGNS SHALL STATE "TOWER CONTROL AREA / UNAUTHORIZED PROVIDED THAT THEY ARE UNDER ESCORT AND IN THE PRESENCE OF AN AREA PRIOR TO OPENING THE AREA TO AIRPORT OPERATIONS. G ACCESS SUBJECT TO FINE". A MINIMUM OF 10 DAYS PRIOR TO THE PRECONSTRUCTION MEETING THE AUTHORIZED SUPERVISOR. KNOWLEDGE OF THE AIRPORTS PROCEDURE'S CONTRACTOR SHALL PROVIDE A LIST OF SUBCONTRACTORS AND BY THE SUPERVISORY PERSONNEL MUST BE DEMONSTRATED PRIOR TO 11. UNDERGROUND UTILITIES 16. PROTECTION MATERIAL SUPPLIERS. THE START OF CONSTRUCTION IT WILL BE NECESSARY FOR THE CONTRACTOR TO MAKE HIS OWN FIELD CONTRACTOR PERSONNEL, VEHICLES, EQUIPMENT AND BARRICADES INVESTIGATION TO DETERMINE THE EXACT LOCATION OF THE A MINIMUM OF 10 DAYS PRIOR TO THE NOTICE TO PROCEED THE DRIVERS OF TRUCKS CONTAINING MATERIAL DELIVERIES (AGGREGATE. SHALL NOT BE ALLOWED WITHIN THE TAXIWAY OBJECT FREE AREA (TOFA) UNDERGROURD UTILITIES AT CRITICAL POINTS, SEE SECTION 70-17 OF THE CONTRACTOR SHALL SUBMIT THE SPCD FOR APPROVAL. CONCRETE, ETC.) SHALL SUBMIT THEIR NAME, DRIVER'S LICENSE NUMBER. STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS FOR SPECIFIC OF ACTIVE TAXIWAYS AND THE RUNWAY SAFETY AREA (RSA) OF ACTIVE TRUCK LICENSE PLATE NUMBER AND NAME OF TRUCKING COMPANY TO REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO THE PRIME CONTRACTOR PRIOR TO ENTERING THE JOBSITE INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. ALLOW FOR THE ORDERLY CONSTRUCTION OF THE NEW IMPROVEMENTS 17. OTHER LIMITATIONS ON CONSTRUCTION NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHILE MAINTAINING AIRCRAFT ACCESS AT ALL TIMES. THE PHASING THE CONTRACTOR'S STORAGE AND STAGING AREA WILL BE AS SHOWN IN IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE IF, DURING CONSTRUCTION, AN EMERGENCY IS DECLARED BY THE SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS THE SITE PLAN AND CONSTRUCTION PHASING PLAN. AIRPORT, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE PAVEMENT INFORMATION THERE IS NO GUARANTEE FITHER EXPRESSED OR F SEQUENCE MAY BE MODIFIED WITH THE APPROVAL OF THE RESIDENT IMPLIED. THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING OF ALL VEHICLES, PERSONNEL AND FOUIPMENT ENGINEER. HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN THE CONTRACTOR SHALL KEEP A RECORD OF THE NAMES OF ALL LINDERGROUND LITH ITIES AS INDICATED ARE REPRESENTATIVE OF THOSE AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT EMPLOYEES ENTERING THE JOB SITE ON A DAILY BASIS. A RECORD OF TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE THE CONTRACTOR SHALL KEEP ALL TRUCKS FOLIPMENT AND MATERIALS EACH SUBCONTRACTOR ENTERING THE JOB SITE SHALL ALSO BE KEPT BY CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION. OFF OF THE EXISTING BUNWAYS AND TAXIWAYS OUTSIDE OF THE THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE DUST CONTROL AT THE CONTRACTOR. OF ALL SLICH FACILITIES. INCLUDING SERVICE CONNECTIONS TO PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF ALL TIMES DURING THE PROJECT DURATION. A WATER TRUCK SHALL BE UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR THE RESIDENT ENGINEER. SHOULD THE CONTRACTOR TRACK ANY DEBRIS THE CONTRACTOR'S MATERIAL AND EQUIPMENT, WHEN NOT IN USE, SHALL REQUIRED TO BE ONSITE DURING ALL CONSTRUCTION OPERATION ONTO EXISTING PAVEMENTS. THIS DEBRIS SHALL BE REMOVED. SHALL NOTIFY THE LITH ITY COMPANY/OWNER OF HIS OPERATIONAL WORKING HOURS, UNLESS WAIVED BY THE AIRPORT, PAYMENT FOR DUST BE STORED IN THE CONTRACTOR'S STAGING AREA. ALL DELIVERIES. PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED IMMEDIATELY WITH A PICK UP SWEEPER. A PICK UP SWEEPER SHALL BE FREEPORT - ALBERTUS CONTROL SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. EQUIPMENT REFUELING, EQUIPMENT MAINTENANCE AND EQUIPMENT INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN REQUIRED TO BE ON SITE AND OPERATE DURING ALL CONSTRUCTION **AIRPORT** TRANSFER SHALL TAKE PLACE WITHIN THE CONTRACTOR'S STAGING LINEXPECTED LITH ITY INTERFERENCE IS ENCOUNTERED DURING OPERATION WORKING HOURS PAYMENT FOR ALL AIRSIDE AND ROADWAY TRAFFIC CONTROL INCLUDING ARFA. CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE FREEPORT, IL BUT NOT LIMITED TO TEMPORARY CONSTRUCTION FENCING. Ε THE CONTRACTOR SHALL PROVIDE WASTE RECEPTACLES THROUGHOUT Ε UTILITY COMPANY, THE OWNER AND THE ENGINEER. ANY SUCH MAINS THE CONTRACTOR WILL BE PERMITTED TO STORE EQUIPMENT AND BARRICADES, SIGNING, AIR OPERATIONS AREA (A.O.A) LATH AND RIBBON AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS. THE WORK ZONE AND MAINTAIN SANITARY FACILITIES FOR EMPLOYEES TO ETC. SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. MATERIALS ONLY AT THE LOCATIONS SHOWN. PARKED EQUIPMENT AND SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE LISE FACILITIES WITHIN THE HANGARS/AIRPORT BUILDINGS SHALL NOT BE MATERIAL STOCKPILES SHALL NOT PENETRATE SURFACES DEFINED BY SATISFACTION OF THE OWNER AND THE ENGINEER. USFD. ALL CONTRACTOR COSTS ASSOCIATED WITH THE REQUIREMENTS LISTED. F.A.R. TITLE 14 PART 77 - OBJECTS AFFECTING NAVIGABLE AIRSPACE. ON THIS SHEET SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT BEFORE INITIATING ANY DIGGING DRILLING OR EXCAVATING ON THE WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS. CITY OF FREEPORT UNLESS A SPECIFIC PAY ITEM IS PROVIDED. ALL PAVEMENTS, DRIVES OR ANY OTHER AREAS UTILIZED BY THE AIRPORT PROPERTY, THE CONTRACTOR SHALL CALL JULI J.E. AND SHALL BE DONE UNDER SUFFICIENT ARTIFICAL AREA LIGHTING TO ALLOW **ILLINOIS** CONTRACTOR FOR HAUL ROADS, STORAGE AREAS AND/OR STAGING CONTACT THE LOCAL FAA OFFICE TO ARRANGE FOR LITILITY LOCATES FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS, LIGHT SHALL 1. COORDINATION AREAS SHALL BE MAINTAINED AND REPAIRED TO THE SAME CONDITION OR SEE SECTION 70-17 OF THE SPECIAL PROVISIONS FOR UTILITY CONTACT CONSIST OF MOVEABLE POLE MOUNTED FLOODLIGHTS AND/OR BETTER THAN THEY WERE PRIOR TO REGINNING CONSTRUCTION NO. PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL SPOTLIGHTS OF SLIFFICIENT NUMBER TO ILLUMINATE WORK AREA INFORMATION ADDITIONAL COMPENSATION WILL BE MADE TO THE CONTRACTOR FOR ATTEND A PRECONSTRUCTION CONFERENCE WITH THE AIRPORT. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER THIS WORK RESIDENT ENGINEER AND ILLINOIS DIVISION OF AFRONALITICS (IDA). THE SHOULD A UTILITY COMPANY OR GOVERNMENT AGENCY BE UNABLE TO LIGHTS MENTIONED AROVE LIGHTING SHALL BE APPROVED BY THE D D COST OF PREPARING FOR AND ATTENDING THE PRECONSTRUCTION LOCATE FACILITIES. THE CONTRACTOR SHALL LOCATE THESE FACILITIES. ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY. IL Proj: 10. ALL VEHICLE AND EQUIPMENT OPERATORS USED BY THE CONTRACTOR CONFERENCE SHALL BE INCIDENTAL TO THE CONTRACT PAYMENT FOR THIS LOCATION SHALL BE INCIDENTAL TO THE SHALL BE PROPERLY TRAINED BY THE CONTRACTOR. IMPROVEMENTS REQUIRING THE LOCATE. THE CONTRACTOR SHALL SUPPLY AND HAVE IN THEIR POSSESSION AT ALL FEP-4489 ON OR BEFORE THE PRECONSTRUCTION CONFERENCE. THE CONTRACTOR TIMES AT LEAST ONE AIRPORT RADIO IN THE EVENT THAT THE AIRPORT 6. WILDLIFE MANAGEMENT SHALL SUBMIT A PROPOSED SCHEDULE FOR THE PROJECT. THE THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL AIRPORT MANAGER NEEDS TO CONTACT THE CONTRACTOR DIRECTLY. THE SCHEDULE SHALL INCLUDE A START AND COMPLETION DATE FOR EACH THE CONTRACTOR SHALL NOTIFY AIRPORT OPERATIONS OR THE OWNED UTILITIES AND SHALL BE CONSIDERED INCIDENTAL TO THE OPERATOR OF SAID RADIO SHALL BE FAMILIAR WITH AIRPORT RADIO APPROVED AS WORKING PLAN ITEM OF WORK. THE SCHEDULE SHALL BE LIPDATED ON A WEEKLY BASIS. RESIDENT ENGINEER IF ANY WILDLIFE IS SEEN ENTERING THE AIRPORT. CONTRACT PROCEDURES AND TUNED INTO GROUND CONTROL FREQUENCY ALL COSTS ASSOCIATED WITH THE SCHEDULE SHALL BE INCIDENTAL TO 2. CONTRACTOR ACCESS GATES SHALL REMAIN CLOSED WHEN THE BROKEN CONCRETE, BROKEN ASPHALT, AND OTHER MISCELLANEOUS THE CONTRACT 12. PENALTIES DEBRIS SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS CONTRACTOR IS NOT WORKING. NONCOMPLIANCE BY THE CONTRACTOR WITH AIRPORT RULES AND 2. PHASING REGULATIONS OR FAILURE TO COMPLY WITH THE AIRPORT'S APPROVED OTHERWISE SPECIFIED. C THE CONTRACTOR SHALL DISPOSE OF ALL TRASH INCLUDING FOOD TOTAL CONTRACT TIME SHALL BE 31 CALENDAR DAYS. CSPP AND THE CONTRACTOR'S APPROVED SPCD MAY RESULT IN FINES AS SCRAPS IN APPROVED CONTRACTOR PROVIDED CONTAINERS. ALLOWED BY LAW. 2. PHASING SHALL BE AS NOTED BELOW AND AS SHOWN ON THE 7. FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT CONSTRUCTION SAFETY AND PHASING PLAN SHEET. 13. SPECIAL CONDITIONS THE CONTRACTOR SHALL PICK UP ANY FOREIGN OBJECT DEBRIS (FOD) ADJACENT CONSTRUCTION MAY IMPACT THE OPERATIONS OF THE REV DATE DESCRIPTION SEEN ON THE AIRFIELD PAVEMENTS 3. AREAS AND OPERATIONS AFFECTED BY CONSTRUCTION CONTRACTOR. SEE THE COORDINATION NOTES FOR ADDITIONAL PROJECT NAME: INFORMATION. ALL RUNWAYS, TAXIWAYS AND APRONS SHALL BE KEPT OPEN TO THE CONTRACTOR SHALL SECURE ALL LOOSE ITEMS FROM VEHICLES AIRCRAFT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED ON THE **CONSTRUCT SOUTHWEST** PRIOR TO DRIVING ON AIRFIELD PAVEMENTS. 14. RUNWAY AND TAXIWAY VISUAL AIDS CONSTRUCTION SAFETY AND PHASING PLAN SHEET. TERMINAL AREA ENTRANCE RUNWAY OR TAXIWAY CLOSURES ARE AS DETAILED IN THE 8. HAZARDOUS MATERIALS (HAZMAT) MANAGEMENT WHEN CONFLICTS ARISE BETWEEN CONSTRUCTION ACTIVITIES AND CONSTRUCTION SAFETY AND PHASING PLAN FOR THIS PROJECT. IF ANY ROAD, PHASE 2 В THE CONTRACTOR SHALL DEVELOP A HAZMAT MANAGEMENT PLAN AND AIRCRAFT OPERATIONS AND SAFFTY, AIRCRAFT OPERATIONS AND SAFFTY RUNWAY OR TAXIWAY CLOSURES ARE REQUESTED BY THE CONTRACTOR KEEP COPIES ON THE JOBSITE OF MATERIAL SAFETY DATA SHEETS (MSDS) SHALL TAKE PRECEDENCE AND SHALL GOVERN. FINAL AUTHORITY IN THE AND APPROVED BY THE AIRPORT, THE CONTRACTOR SHALL USE MARKING, FOR ALL MATERIALS HANDLED ON THE JOBSITE. APPROVAL OF CONSTRUCTION SEQUENCING LIES WITH THE AIRPORT. LIGHTING AND SIGNS THAT FOLLOW THE REQUIREMENTS OF FAA AC SEQUENCE OF 150/5370-2(LATEST VERSION). 9. NOTIFICATION OF CONSTRUCTION ACTIVITIES AIRCRAFT OPERATIONS HAVE THE RIGHT-OF-WAY ON THE AIRFIELD. ALL **CONSTRUCTION NOTES** CONSTRUCTION TRAFFIC SHALL IMMEDIATELY YIELD TO ONCOMING THE CONTRACTOR SHALL PROVIDE A 24 HOUR EMERGENCY CONTACT 15. HAZARD MARKING AND LIGHTING AND DETAILS AIRCRAFT AT ALL TIMES PERSON AND PHONE NUMBER ORANGE -THE CONTRACTOR SHALL FURNISH FRECT, AND MAINTAIN MARKINGS AND DESIGNED ASSOCIATED LIGHTING OF OPEN TRENCHES, EXCAVATIONS, TEMPORARY SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARY THE CONTRACTOR SHALL GIVE A MINIMUM OF 72 HOURS NOTICE TO CMT-MLI CMT-MLI CMT-MLI STOCKPILES, AND HIS/HER CONSTRUCTION EQUIPMENT RELOCATE FOUIPMENT AT ANY TIME TO ALLOW AN AIRCRAFT TO PASS. AIRPORT OPERATIONS PRIOR TO CLOSING ANY PAVEMENTS SO THAT THE CONTRACTOR SHALL DO SO IMMEDIATELY AT NO EXTRA COST TO THE PROPER NOTAMS MAY BE ISSUED BY THE AIRPORT PROJECT NO : 21001617.00 ALL CONSTRUCTION FOUIPMENT SHALL BE FLAGGED AND/OR LIGHTED IN CONSTRUCTION EQUIPMENT Α DATE: SEPTEMBER 22, 2023 ACCORDANCE WITH FAA ADVISORY CIRCULAR 150/5370-2(LATEST EDITION) AND TRUCK SIGNAL FLAG 3. FOR ANY EQUIPMENT USED BY THE CONTRACTOR WITH A HEIGHT AND 150/5210-5(I ATEST EDITION) AT ALL TIMES WHILE OPERATING ON 4. PROTECTION OF NAVIGATION AIDS (NAVAIDS) GREATER THAN 25', THE CONTRACTOR SHALL PROVIDE TO THE AIRPORT NOT TO SCALE 6 AIRPORT PROPERTY. THE MAXIMUM FOUIPMENT HEIGHT IS 25. THE TYPE OF EQUIPMENT, TOTAL HEIGHT, AND LOCATION WHERE THE THE CONTRACTOR SHALL REMAIN CLEAR OF THE ILS CRITICAL AREAS AND EQUIPMENT WILL BE USED. THE AIRPORT WILL SUBMIT FAA FORM 7460-1 OTHER NAVAIDS FACILITIES AT ALL TIMES. BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE SHEET 6 OF 25 SHEETS















































STORM WATER POLLUTION PREVENTION PLAN

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE REGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEFRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING. WHICH WILL BE AT THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS

SITE DESCRIPTION:

Н

G

Ε

D

C

В

Α

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

THIS PROJECT CONSISTS OF REHABILITATION OF EXISTING BITLIMINOUS PAVEMENT AT THE FREEPORT-ALBERTUS AIRPORT. THE PROJECT INCLUDES BITUMINOUS MILLING, BITUMINOUS PAVING, TURF SHOULDER ADJUSTMENTS, PAVEMENT MARKING AND OTHER MISCELLANEOUS CONSTRUCTION WORK

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS GRUBBING, EXCAVATION AND GRADING

PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEAN-UP OF TEMPORARY EROSION CONTROL. SUCH AS

REMOVAL, ADJUSTMENTS AND INSTALLATION OF MISCELLANEOUS ITEMS.

BITUMINOUS PAVEMENT MILLING AND PAVING

TURF SHOULDER ADJUSTMENT, SEEDING AND MULCHING

INSTALLATION OF NEW PAVEMENT MARKING

REMOVAL AND DISPOSAL OF TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES.

AREA OF CONSTRUCTION SITE

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 4 ACRES OF WHICH 1.10 ACRES WILL BE

OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS:

- INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS.
- PROJECT PLAN DOCUMENTS, SPECIFICATION AND SPECIAL PROVISIONS, AND PLAN DRAWINGS INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE

THE CONSTRUCTION SITE DRAINS INTO THE PECATONICA RIVER THROUGH A STORM SEWER SYSTEM

EROSION AND SEDIMENT CONTROL:

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION:

THE DRAWINGS SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE: TEMPORARY SEEDING, PERMANENT SEEDING, MULCHING, SOD, PROTECTION OF TREES, PRESERVATION OF NATURAL VEGETATION, AND ALL OTHER APPROPRIATE MEASURES AS DIRECTED BY THE ENGINEER, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY

AREAS OF EXISTING VEGETATION (WOOD AND GRASSLANDS) OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE IDENTIFIED BY THE ENGINEER FOR PRESERVING AND SHALL BE PROTECTED FROM CONSTRUCTION

DEAD, DISEASED, OR UNSUITABLE VEGETATION WITHIN THE SITE SHALL BE REMOVED AS DIRECTED BY THE

AS SOON AS REASONABLE ACCESS IS AVAILABLE TO ALL LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, INLET PROTECTIONS SHALL BE INSTALLED AS CALLED OUT IN THE PLAN AND DIRECTED BY THE ENGINEER

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILR10, ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER). PARKING OF VEHICLES OR CONSTRUCTION FOUIPMENT. STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES.

WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVEN UNNECESSARY SOIL EROSION.

EARTH STOCKPILES SHALL BE <u>TEMPORARILY SEEDED</u>, <u>AT THE CONTRACTOR'S EXPENSE</u>, IF THEY ARE TO REMAIN UNUSED FOR MORE THAN SEVEN (7) DAYS.

THE DOWN STREAM SIDE OF ALL STOCKPILES SHALL BE ENCOMPASSED WITH EROSION CONTROL BARRIER.

AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:

A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS

CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS WITHIN THE STAGING AREA. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR

THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT PERIODICALLY DURING CONSTRUCTION ACTIVITIES INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2" OR GREATER OR GOUIVALENT SNOWFALL AND DURING WINTER SHUTDOWN PERIOD. THE PROJECT SHALL ADDITIONALLY BE INSPECTED BY THE RESIDENT ENGINEER ON A BI-WEEKLY BASIS TO DETERMINE THAT THE EROSION AND SEDIMENT CONTROL EFFORTS ARE IN PLACE AND EFFECTIVE AND IF OTHER EBOSION CONTROL WORK IS NECESSARY

SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL RE DISPOSED OF ON SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR UNCLASSIFIED EXCAVATION AND EROSION CONTROL ITEMS

THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCLUDED IN THE UNIT BID PRICE FOR VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING SOIL CONTAMINATION FROM BLILLDING MATERIALS. FERTILIZERS, CHEMICALS, PAVEMENT MARKING, WASTE PILES, FUEL CONTAINMENT, AND ANY OTHER POTENTIAL HAZARDOUS MATERIALS THAT MAY EXIST ONSITE.

NO DEDICATED CONCRETE OR ASPHALT BATCH PLANTS SHALL BE LOCATED ON THIS SITE.

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED

COST OF MAINTAINING THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE INCLUDED INCLUDED IN THE UNIT BID PRICE FOR THE VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RE-SEEDED AND/OR SODDED.

MAINTENANCE AFTER CONSTRUCTION:

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE OF TEMPORARY AND PERMANENT EROSION CONTROL SYSTEMS UP TO THIS DATE WILL BE REQUIRED BY

PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL COMPLETE AND SUBMIT A "NOTICE OF INTENT (NOI)" PROPERLY SIGNED TO THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY.

PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL POST A SIGN OR OTHER NOTICE NEAR THE MAIN ENTRANCE OF THE CONSTRUCTION SITE. IF THIS IS NOT POSSIBLE, THEN IT MAY BE PERMITTED TO POST THIS NOTICE IN A LOCAL PUBLIC BUILDING. THE SIGN OR NOTICE MUST CONTAIN THE FOLLOWING:

- A COPY OF THE COMPLETED NOTICE OF INTENT (NOI) AS SUBMITTED TO THE IEPA 2. THE LOCATION OF THE SWPPP AND NAME AND 24/7 TELEPHONE NUMBER OF THE CONTACT PERSON.

THROUGHOUT CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN AND UPDATE AN "AS-BUILT" SET OF STORM WATER POLLUTION PREVENTION PLANS IN THE PROJECT FILES. THE SWPPP SHALL BE UPDATED WITHIN 7-DAYS OF ANY MODIFICATIONS TO THE PLANS. THE SWPPP AND ALL REVISIONS SHALL BE RETAINED FOR THREE YEARS AFTER FINAL STABILIZATION OF THE SITE, WHICH SHALL BE DEFINED AS VEGETATION COVER OF AT LEAST 70% OF HISTORIC

A STORM WATER POLITITION PREVENTION PLAN EROSION CONTROL INSPECTION REPORT (FORM RC 2259) SHALL RE RE COMPLETED WITH INSPECTION FREQUENCIES AS OUTLINED HEREIN. SWPPP REPORTS SHALL BE RETAINED FOR THREE YEARS AFTER THE DATE OF FINAL STABILIZATION AS DEFINED HEREIN.

IF ANY VIOLATION OF THE PROVISIONS OF THE PLAN IS IDENTIFIED DURING THE CONDUCT OF THE CONSTRUCTION COVERED IN THIS PLAN, THE ENGINEER AND/OR CONTRACTOR SHALL COMPLETE AND FILE AN "INCIDENT OF NONCOMPLIANCE (ION)" REPORT FOR THE IDENTIFIED VIOLATION. THE FORMS SHALL BE AS PROVIDED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY, AND SHALL INCLUDE SPECIFIC INFORMATION ON THE INCIDENT THAT CAUSED NONCOMPLIANCE, ACTIONS THAT WERE TAKEN TO CORRECT THE NONCOMPLIANCE AND TO PREVENT ITS' REOCCURRENCE, AND A STATEMENT DETAILING ANY ENVIRONMENTAL IMPACT WHICH MAY HAVE RESULTED FROM THE NONCOMPLIANCE. ALL REPORTS OF NONCOMPLIANCE SHALL BE SIGNED BY A RESPONSIBLE AUTHORITY IN ACCORDANCE WITH PART VI. G. OF THE GENERAL PERMIT

AFTER PROJECT FINAL ACCEPTANCE, THE CONTRACTOR SHALL COMPLETE AND SUBMIT A "NOTICE OF TERMINATION (NOT)" FORM PROPERLY SIGNED TO THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY, FORMS FOR THE IEPA SHALL BE MAILED TO THE FOLLOWING ADDRESS

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL, MAIL CODE #15
ATTN: PERMIT SECTION 1021 NORTH GRAND AVENUE EAST P O BOX 19276 SPRINGFIELD, ILLINOIS 62794-9276

| NPDES PERMIT # | |
|----------------|--|
| DATE ISSUED | |
| DATE EXPIRED | |
| | |

GENERAL NOTES FOR SOIL EROSION AND SEDIMENT CONTROL

- ALL TREE PROTECTION, SEDIMENT CONTROL MEASURES, AND PERMANENT AND TEMPORARY STORM WATER PRACTICES
- NO WORK SHALL BE PERFORMED IN FLOWING WATER. WORK IN AND NEAR FLOWING WATER SHALL BE ISOLATED FROM CONCENTRATED FLOWS OR STREAM FLOWS AT ALL TIMES. THE USE OF EARTHEN MATERIAL FOR ISOLATION WILL NOT BE
- CONSTRUCTION MATERIALS AND/OR OTHER STOCKPILES SHALL NOT BE LOCATED ON STREAM BANKS NOR IN THE PATH OF
- TEMPORARY EROSION CONTROL DEVICES SHALL BE CONSTRUCTED AS SHOWN ON THE PLANS OR AS DIRECTED BY THE
- PERMANENT SEEDING SHALL BE USED WHENEVER POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PROLONG GRADING OR SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDED AT ONE TIME.
- THE CONTRACTOR SHALL INSPECT ADJACENT STREETS DAILY AND CLEAN ADJACENT STREETS WHEN NECESSARY.
- SHOULD IT BE NECESSARY TO REMOVE ANY EROSION CONTROL DEVICES FOR CONSTRUCTION REASONS. THE CONTRACTOR SHALL FIRST OBTAIN PERMISSION AND SHALL REPLACE AND/OR REPAIR THE REMOVED DEVICES THE SAME DAY. THE COST OF REMOVING AND REPLACING THE DEVICE SHALL BE CONSIDERED INCIDENTAL TO THE CONTRAC
- ALL OTHER SOIL FROSION AND SEDIMENT CONTROL DEVICES AND MEASURES DEEMED NECESSARY BY THE RESIDENT RELOTINE TO SUE PROSIDE AND SEDIMENT CONTROL DEVICES AND MERASORES DEEMED NECESSARY BY THE RESIDENT ENGINEER, STEPHENSON COUNTY, FREEPORT-ALBERTUS AIRPORT, IDOT DIVISION OF AERONAUTICS, AND THE IEPA SHALL BE IMPLEMENTED IMMEDIATELY UPON NOTIFICATION OF THE CONTRACTOR.
- THE CONTRACTOR SHALL PROVIDE LOCATIONS FOR CONCRETE TRUCK WASHOUT, AS APPROVED BY THE ENGINEER, PRIOR TO ANY CONCRETE POURS. THESE LOCATIONS SHALL NOT BE NEAR ANY STREAM OR BODY OF WATER. LOCATIONS SHALL BE APPROVED BY THE ENGINEER PRIOR TO ANY CONCRETE POURS. ADDITIONALLY THE CONTRACTOR SHALL PROVIDE ADEQUATE FACILITIES TO WASHOUT PAVING FOLIPMENT AND FINISHING TOOLS. ALL WASTE WATER AND EXCESS CONCRETE MATERIALS SHALL BE CONTAINED BY AN APPROVED CONCRETE WASHOUT FACILITY
- 10. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES TO ENSURE THAT EROSION CONTROL MEASURES ARE NSISTENT BETWEEN ALL PROJECT PHASES AND ALL SUB-CONTRACTORS
- 11. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PROTECT WETLANDS TO REMAIN FROM DAMAGE BY SEDIMENT. CONSTRUCTION EQUIPMENT, OR BY HIS PERSONNEL, THE CONTRACTOR SHALL ASSURE THAT DEBRIS OR ANY CONSTRUCTION MATERIAL IS NOT DISPOSED OF IN THE WETLANDS.
- 12. WATER PUMPED OR OTHERWISE DISCHARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE FILTERED
- 13. SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON A REGULAR BASIS. SEDIMENT SHALL BE REMOVED FROM EROSION CONTROL SYSTEMS WHEN THE HEIGHT OF THE SEDIMENT EXCEEDS ONE-HALF OF THE HEIGHT OF THE DEVICE OR AS RECOMMENDED BY THE MANUFACTURER,
- 14. ALL EROSION CONTROL MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY THROUGHOUT THE PERIOD OF LAND DISTURBANCE UNTIL PERMANENT SOIL EROSION AND SEDIMENT CONTROL MEASURES ARE OPERATIONAL
- 15. THE CONDITION OF THE CONSTRUCTION SITE FOR WINTER SHUTDOWN SHALL BE ADDRESSED FARLY IN THE FALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILLZED WITH TEMPORARY AND/OR PERMANENT VEGETATIVE COVER. ALL OPEN AREAS THAT ARE TO REMAIN IDLE THROUGHOUT THE WINTER SHALL RECEIVE TEMPORARY FROSION CONTROL MEASURES INCLUDING TEMPORARY SEEDING, MULCHING AND/OR FROSION CONTROL BLANKET PRIOR TO THE END OF THE FALL GROWING SEASON. THE AREAS TO BE WORKED BEYOND THE END OF THE GROWING SEASON MUST INCORPORATE SOIL STABILIZATION MEASURES THAT DO NOT RELY ON VEGETATIVE COVER SUCH AS EROSION CONTROL BLANKET AND HEAVY MULCHING.
- 16. PERMANENT STABILIZATION SHALL BE COMPLETED WITHIN 7 DAYS FOR AREAS WHERE WORK IS COMPLETED

| CONTRACTOR CERTIFICATION STATEMENT | Т |
|------------------------------------|---|

THIS CERTIFICATION STATEMENT IS A PART OF THE STORM WATER POLITION PREVENTION PLAN FOR THE PROJECT DESCRIPED BELOW IN ACCORDANCE WITH NPDES PERMIT NO. ILR10 ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY

PROJECT INFORMATION:

MARKED: CONSTRUCT SOUTHWEST TERMINAL AREA ENTRANCE ROAD, PHASE 2 ROUTE: FREEPORT-ALBERTUS AIRPORT PROJECT NUMBER: FEP-4489 SECTION: 21 CONTRACT NUMBER: FR047 COUNTY: STEPHENSON

I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT (ILR10) THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION.

| SIGNATURE: | DATE: |
|--|--|
| PRINTED NAME: | TITLE: |
| NAME OF FIRM: | |
| STREET ADDRESS: | |
| CITY, STATE, ZIP: | |
| PHONE NUMBER: | |
| THE INFORMATION WITHIN THE DOVING HALL BE CO | NADI ETED DV THE CONTRACTOR AFTER THE AWAI |

OBTAIN THE REQUIRED NPDES PERMIT FROM IEPA. COMPLETION OF THIS IS A CONTRACT REQUIREMENT

| RE | CORD OF SITE DISTURBANCE AND STABILIZATION |
|--------------------------------------|--|
| MAJOR GRADING ACTIVITIES: LOCATION: | BEGINNING DATE:COMPLETION DATE: |
| MAJOR GRADING ACTIVITIES: LOCATION: | BEGINNING DATE:COMPLETION DATE: |
| SITE STABILIZATION: LOCATION: | BEGINNING DATE:COMPLETION DATE: |
| SITE STABILIZATION: LOCATION: | BEGINNING DATE:COMPLETION DATE: |
| CONSTRUCTION CEASED: EXPLANATION: | BEGINNING DATE:COMPLETION DATE: |

THE INFORMATION WITHIN THIS BOX SHALL BE COMPLETED BY THE CONTRACTOR AS CONSTRUCTION PROGRESSES IN ACCORDANCE WITH THE NPDES GENERAL PERMIT FOR STORMWATER DISCHARGES. THIS INFORMATION MAY ALSO BE NOTED DIRECTLY ON THE SWPPP SITE MAP.





FREEPORT - ALBERTUS **AIRPORT** FREEPORT, IL

Ε

D

CITY OF FREEPORT **ILLINOIS**

> IL Proj: FEP-4489

| | BY: | | | | |
|--------------|-----|---------|-------------|--|--|
| | = | | | | |
| | | | | | |
| \mathbb{C} | _ | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | REV | DATE | DESCRIPTION | | |
| | PRC | JECT NA | ME: | | |

CONSTRUCT SOUTHWEST TERMINAL AREA ENTRANCE ROAD, PHASE 2

SHEET TITLE:

SWPPP NOTES

DESIGNED DRAWN: CHECKED: CMT-MLI CMT-MLI CMT-MLI PROJECT NO : 21001617.00 DATE: SEPTEMBER 22, 2023

SHEET 24 OF 25 SHEETS

8

6

5

