



**LEGEND**

- PERIMETER EROSION BARRIER
- INLET FILTERS
- SODDING, TOPSOIL FURNISH AND PLACE 4"

**VILLAGE OF GLENVIEW EROSION CONTROL NOTES**

1. ALL VEGETATIVE AND STRUCTURAL EROSION CONTROL PRACTICES SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE MINIMUM STANDARDS AND SPECIFICATIONS OF THE "ILLINOIS PROCEDURES AND STANDARDS FOR URBAN SOIL EROSION AND SEDIMENTATION CONTROL" AND THE "STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL" OF THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY (IEPA).
2. THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES PERIODICALLY AND AFTER EACH SOIL RUNOFF PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF SAID MEASURES SHALL BE MADE IMMEDIATELY (THE SAME DAY).
3. ALL SLOPES SHALL BE COVERED WITH SOD AS SOON AS GRADING AND PLACEMENT OF TOPSOIL HAS BEEN COMPLETED. THE LIMITS OF THE SODDING SHALL BE THE LIMITS OF GRADING AND/OR AS DIRECTED BY THE ENGINEER.
4. INLET FILTERS SHALL BE PLACED ON ALL CATCH BASINS, INLETS AND MANHOLES WITH OPEN GRATES.

COPYRIGHT © 2011 BY BAXTER & WOODMAN, INC. 110025-EC-WILLOW.shd  
 DATE PLOTTED: 03/17/2011 9:17:20 AM  
 FILE: 110025-EC-WILLOW.shd  
 PLOT: 110025-EC-WILLOW.shd



DESIGNED - CSK	REVISED - PER IDOT COMMENTS 6-20-11
DRAWN - RKM	REVISED - PER ISTHA COMMENTS 6-20-11
CHECKED - TLH	REVISED -
DATE - 3-1-2011	FILE - 110025-EC-WILLOW.shd

**VILLAGE OF GLENVIEW, ILLINOIS  
F.A.P. 305 (WILLOW ROAD) SIDEWALK IMPROVEMENTS**

**EROSION CONTROL PLAN**

SCALE: 1" = 40'      STA.      TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	11-00177-00-SW	COOK	21	7
JOB No. C-91-448-11		CONTRACT NO. 63606		
FED. ROAD DIST. NO. 1 ILLINOIS/FED. AID PROJECT TE-00018591				