


**TOP VIEW** 




## ADJUSTABLE TIE



EYE BOLT TIE




CANOPY TIE




U BOLT TIE

540-22

THE CULVERT TIES SHALL BE INCLUDED IN THE COST OF THE CONCRETE PIPE CULVERTS OR THE PRECAST CONCRETE BOX CULVERT. THE MECHANICAL TIES SHALL BE ON THE OUTSIDE OF THE CULVERT. THE NUTS AND WASHERS SHALL BE PLACED ON THE INSIDE OF THE CULVERT AND COVERED WITH MASTIC JOINT SEALER CONFORMING TO ARTICLES 1055 OR 1056 IN THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.






PLACEM	PLACEMENT OF HOLES					
BOX CULVERT	PIPE SIZE	THREAD				
		DIAMETER				
FEET	INCHES	INCHES				
	12	5/8				
	15	ROLLED				
	18	THREADS				
	21	(SEE				
	24	NOTE 4)				
	27	·				
	30					
3 x 2	33					
3 x 3	36	3/4				
4 x 2	42	CUT				
4 x 3	48	OR				
4 x 4	54	ROLLED				
5 x 3	60					
5 x 4	66					
5 x 5	72					
6 x *	78					
7 x *	84	1				
8 x *	90	CUT				
9 x *	96	OR				
10 x *	102	ROLLED				
	108					
	120					
	132					
11 x *	138	1 1/4				
AND GREATER	AND GREATER					

## NOTES:

- 1. HOLES SHALL BE CAST-IN OR DRILLED 16" FROM OUTSIDE EDGE OF JOINT.
- 2. NUTS AND WASHERS ARE NOT REQUIRED ON INSIDE OF 27" DIAMETER PIPE OR LESS.
- 3. TIES ARE NOT REQUIRED FOR BELL PIPE 24" AND SMALLER. ON OTHER SIZES TIE MAY BE INSERTED FROM INSIDE.
- 4. CUT THREADS MAY BE USED IF WASHER AND NUT ARE USED.
- 5. PIPE SIZE LISTED IS INSIDE DIAMETER OF ROUND PIPE OR EQUIVALENT DIAMETER OF PIPE ARCH OR ELLIPTICAL.
- 6. GALVANIZING OF TIES IS REQUIRED.









STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** 

SCALE:

ME	ECHANICAL JOINTS FOR CONCRETE PIPE AND BOX CULVERTS				
	SHEET	OF	SHEETS	STA.	TO STA.

- A RTE	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.			
			CONTRACT NO.					
ILLINOIS FED. A			ID PROJECT					